

SPANISH TRAILS UNIT 2 WEST
BEXAR COUNTY, TX

: 11/13/25 Addendum #4

Job # 12044-06

ITEM NO.	BID ITEM				
		UNIT	QUANTITY	UNIT PRICE	BID TOTAL
	ONSITE STREETS				
	Remove Header Curb & Barricade Posts	LF	40		
	10" Aggregate Base (Local A)	SY	7,580		
	19" Aggregate Base (Local B)	SY	1,152		
	2" Type D HMA (< 10,000 SY) (Local A)	SY	6,836		
	3" Type D HMA (< 10,000 SY) (Local B)	SY	1,064		
	Lime Treated Subgrade (6" Compacted Depth)	SY	8,732		
	Lime (<100 TON)	TON	118		
	Prime Coat	GAL	1,746		
	Tack Coat	GAL	873		
	7" Concrete Curb	LF	4,284		
	Concrete Sidewalk	SY	239		
	Header Curb	LF	60		
	Barricade Posts	EA	12		
	Sidewalk Ramps (Developer Responsibility)	EA	8		
	Signage & Striping (onsite)	LS	1		
	SUB-TOTAL				
	SANITARY SEWER				
	8" Sanitary Sewer Pipe (6'-10' Deep) (SDR-26)	LF	1,820		
	8" Sanitary Sewer Pipe (10'-14' Deep) (SDR-26)	LF	1,081		
	Tie To Existing Manhole & Adjust MH Top	EA	1		
	Tie To Existing Manhole w/ External Drop	EA	1		
	Standard Manhole	EA	9		
	Manhole Extra Depth	VF	27.6		
	Concrete Ring Encasement	EA	9		
	8" x 6" Wye	EA	86		
	6" Sanitary Sewer Lateral (SDR-26)	LF	3,315		
	Vertical Stacks	VF	3.6		
	Trench Excavation Protection	LF	2,901		
	Camera Testing	LF	2,901		
	SUB-TOTAL				
	WATER DISTRIBUTION				
	8" PVC C-900 Class 235 DR 18	LF	2,336		
	8" Gate Valve, MJ w/Valve Box	EA	8		
	Standard Fire Hydrant Assembly	EA	6		
	Ductile Iron Fittings	Ton	0.8		
	¾" Single Service (Short) w/ 5/8" Water Meter	EA	51		
	¾" Single Service (Long) w/ 5/8" Water Meter	EA	40		
	2" Blowoff (Temporary)	EA	1		
	2" Blowoff (Permanent)	EA	2		
	Hydrostatic Testing	LS	1		
	Chlorination	LF	2,336		
	Trench Excavation Protection	LF	2,336		
	Joint Restraints	LS	1		
	Plastic Meter Box w/Lid	EA	91		
	SUB-TOTAL				
	EARTHWORK, CLEARING, AND SWPPP				
	Street Excavation	CY	8,914		
	Street Embankment	CY	110		
	Channel Excavation	CY	6,371		
	Channel Embankment	CY	5		
	Lot Excavation	CY	4,884		
	Lot Embankment	CY	4,393		
	Export (Haul-off)	CY	10,661		
	TPDES	LS	1		
	Clearing (Streets)	AC	2.6		
	Clearing (Lots/Offsite Easements)	AC	11.7		
	SUB-TOTAL				

	ONSITE DRAINAGE				
	6" Concrete Rip-Rap	SY	1,128		
	Rock Rubble	SY	5		
	Hydromulch (80% vegetation)	SY	4,714		
	SUB-TOTAL				
	TRAFFIC SIGNAL& PVMT MARKINGS (SINCLAIR INTERSECTION IMPROVEMENTS)				
	DRILL SHAFTS (36 IN)	LF	39		
	CONCRETE CURB	LF	44		
	CONCRETE SIDEWALKS (4")	SY	33		
	CONCRETE SIDEWALKS (TxDOT TYPE 3 CURB RAMP)	SF	300		
	CONCRETE SIDEWALKS (TxDOT TYPE 6 CURB RAMP)	SF	281		
	ELIMINATE EXISTING PAVEMENT MARKINGS (4 IN)	LF	1,806		
	ELIM EXT PAV MRK & MRKS (24")	LF	18		
	4 INCH WIDE YELLOW LINE	LF	1,048		
	4 INCH WIDE WHITE LINE (SOLID)	LF	40		
	8 INCH WIDE WHITE LINE (SOLID)	LF	100		
	24 INCH WIDE WHITE LINE (SOLID)	LF	378		
	12 INCH WIDE BLACK LINE (SOLID)	LF	620		
	PAVEMENT MARKING (RIGHT WHITE ARROW)	EA	2		
	PAVEMENT MARKING (LEFT WHITE ARROW)	EA	2		
	PAVEMENT MARKER (TYPE II C-R)	EA	28		
	CONDUIT (PVC SCHEDULE 40) (2 IN)	LF	325		
	CONDUIT (PVC SCHEDULE 40) (3 IN)	LF	315		
	CONDUIT (PVC SCHEDULE 40) (2 IN) (BORE)	LF	445		
	CONDUIT (PVC SCHEDULE 40) (3 IN) (BORE)	LF	630		
	ELECTRICAL CONDUCTORS (NO. 6) (BARE)	LF	1,835		
	ELECTRICAL CONDUCTORS (NO. 8) (BARE)	LF	10		
	ELECTRICAL CONDUCTORS (NO. 6) (INSULATED)	LF	20		
	TRAY CABLE (12 AWG) (3 CONDUCTOR)	LF	590		
	INSTALL GROUND BOXES TYPE D (162922) W/ APRON	EA	5		
	ELECTRICAL SERVICE (TYPE D) (120 / 240V)	EA	1		
	BATTERY BACKUP SYSTEM (EXTERNAL CABINET)	EA	1		
	TYPE 332 CONTROLLER FOUNDATION	EA	1		
	INSTALLATION OF HIGHWAY TRAFFIC SIGNALS(ISOLATED)	EA	1		
	REMOVING TRAFFIC SIGNALS	EA	1		
	INSTALL VEHICLE SIGNAL HEAD WITH BACK PLATE(3 SEC)	EA	3		
	INSTALL VEHICLE SIGNAL HEAD WITH BACK PLATE(4 SEC)	EA	4		
	INSTALL VEHICLE SIGNAL HEAD WITH BACK PLATE(5 SEC)	EA	1		
	INSTALL PEDESTRIAN SIG HEAD (12 IN) LED (2 IND)	EA	6		
	TRAFFIC SIG CBLs(TYPE A)(16 AWG) (3 COND)(STRNDED)	LF	775		
	TRAFFIC SIG CBLs (TYPE A)(14 AWG)(4 COND)	LF	615		
	TRAFFIC SIG CBLs (TYPE A)(14 AWG)(9 CONDUCTOR)	LF	2,700		
	INSTALL TRAF SIG POLE ASEM(SINGLE 40' MA)ILSN& LUM	EA	2		
	INSTALL TRAF SIG POLE ASEM(SINGLE 48' MA)ILSN& LUM	EA	1		
	INSTALL PEDESTAL POLE ASSEMBLY	EA	6		
	INSTALL AUDIBLE PED. DETECT. (2 IN TACTILE PUSH BTN AND SIGN)	EA	6		
	INSTALL PED DETECTOR CONTROLLER UNIT	EA	1		
	INST INTRNL LGT ST NAME SIG(DBLE SIDE)(LED)(6 FT)	EA	2		
	INST INTRNL LGT ST NAME SIG(DBLE SIDE)(LED)(6 FT)	EA	1		
	INSTALL RADAR ADVANCE DETECTION DEVICE	EA	2		
	INSTALL RADAR DETECTION DEVICE COMMUNICATION CABLE	LF	1,200		
	INSTALL RADAR PRESENCE DETECTION DEVICE	EA	3		
	PORTABLE CHANGEABLE MESSAGE SIGN	DAY	42		
	TMA (STATIONARY)	DAY	3		
	INSTALL ITS TRAFFIC MONITORING CAMERA ASSEMBLY	EA	1		
	INSTALL ITS TRAFFIC MONITORING CAMERA CABLING	LF	115		
	SUB-TOTAL				

	S WW WHITE (WIDENING IMPROVEMENTS)				
0100-7002	PREPARING ROW	STA	12.0		
0104-7013	REMOV CONC (SIDEWALK, RAMP OR SUP)	SY	474		
0104-7016	REMOV CONC (CURB)	LF	425		
0105-7009	RMV (9"-13") TRT/UNTRT BASE & ASPH PAV	SY	3048		
0110-7001	EXCAV (ROADWAY)	CY	1267		
0132-7004	EMBANK (FNL)(DC)(TY B)	CY	24		
0160-7002	FURN & PLACE TOPSOIL (4")	SY	56		
0164-7002	BROADCAST SEED (PERM_RURAL_CLAY)	SY	56		
0168-7001	VEGETATIVE WATERING	TGL	3		
0260-7005	LIME (COM OR QK)(SLURRY)	TON	38.0		
0260-7006	LIME TRT (EXIST MATL)(6")	SY	3297		
0310-7013	PRIME COAT(MC-30 OR AE-P)	GAL	660.00		
0341-7006	D-GR HMA TY-B PG70-22	TON	1966.0		
0341-7058	D-GR HMA TY-D SAC-B PG76-22	TON	1097.0		
0341-7082	TACK COAT	GAL	1556.00		
0354-7082	PLANE ASPH CONC PAV(2.5")	SY	5981		
0479-7001	ADJUSTING MANHOLES	EA	1		
0502-7001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	4		
0505-7001	TMA (STATIONARY)	DAY	92		
0505-7003	TMA (MOBILE OPERATION)	DAY	30		
0506-7020	CONSTRUCTION EXITS (INSTALL) (TY 1)	SY	312		
0506-7024	CONSTRUCTION EXITS (REMOVE)	SY	312		
0506-7034	CONSTRUCTION PERIMETER FENCE	LF	890		
0506-7039	TEMP SEDMT CONT FENCE (INSTALL)	LF	538		
0506-7041	TEMP SEDMT CONT FENCE (REMOVE)	LF	538		
0506-7043	BIODEG EROSN CONT LOGS (INSTL) (8")	LF	25		
0506-7046	BIODEG EROSN CONT LOGS (REMOVE)	LF	25		
0512-7009	PORT CTB (FUR & INST)(LOW PROF)(TY 1)	LF	320		
0512-7010	PORT CTB (FUR & INST)(LOW PROF)(TY 2)	LF	80		
0512-7033	PORT CTB (MOVE)(LOW PROF)(TY 1)	LF	300		
0512-7035	PORT CTB (MOVE)(LOW PROF)(TY 3)	LF	40		
0512-7057	PORT CTB (REMOVE)(LOW PROF)(TY 1)	LF	320		
0512-7058	PORT CTB (REMOVE)(LOW PROF)(TY 2)	LF	80		
0529-7001	CONC CURB (TY 1)	LF	770		
0531-7002	CONC SIDEWALKS (5")	SY	446		
0531-7006	CURB RAMPS (TY 2)	EA	2		
0662-7068	WK ZN PAV MRK REMOV (W)6"(SLD)	LF	7680		
0662-7100	WK ZN PAV MRK REMOV (Y)6"(SLD)	LF	0		
0666-7024	REFL PAV MRK TY I (W)8"(SLD)(100MIL)	LF	215		
0666-7036	REFL PAV MRK TY I (W)24"(SLD)(100MIL)	LF	22		
0666-7042	REFL PAV MRK TY I (W)(ARROW)(100MIL)	EA	2		
0666-7066	REFL PAV MRK TY I (W)(WORD)(100MIL)	EA	2		
0666-7132	REFL PAV MRK TY I(Y)(MED NOSE)(100MIL)	EA	3		
0666-7168	RE PM TY II (W) 4" (BRK)	LF	537		
0666-7175	RE PM TY II (W) 6" (SLD)	LF	2147		
0666-7179	RE PM TY II (W) 8" (SLD)	LF	215		
0666-7184	RE PM TY II (W) 24" (SLD)	LF	22		
0666-7186	RE PM TY II (W) (ARROW)	EA	2		
0666-7194	RE PM TY II (W) (WORD)	EA	2		
0666-7210	RE PM TY II (Y) 4" (SLD)	LF	3485		
0666-7220	RE PM TY II (Y) (MED NOSE)	EA	3		
0666-7402	REFL PAV MRK TY I (W)4"(BRK)(100MIL)	LF	2		
0666-7411	REFL PAV MRK TY I (W)6"(SLD)(100MIL)	LF	2147		
0666-7417	REFL PAV MRK TY I (Y)4"(SLD)(100MIL)	LF	3485		
0672-7002	REFL PAV MRKR TY I-C	EA	11		
0672-7004	REFL PAV MRKR TY II-A-A	EA	210		
0677-7001	ELIM EXT PM & MRKS (4")	LF	6920		
	SUB-TOTAL				
	CONDUITS				
	1-6" SCH 80 & 2-4" SCH 40 Bundle	LF	1,050		
	2-6" SCH 80 & 2-4" SCH 40 Bundle	LF	20		
	SUB-TOTAL				
	MISC				
	Testing	LS	1		
	Construction Staking	LS	1		
	SUB-TOTAL				

	BID ALTERNATE #1 -LOOP 410 (WIDENING IMPROVEMENTS)				
0100-7002	PREPARING ROW	STA	3.0		
0105-7009	RMV (9"-13") TRT/UNTRT BASE & ASPH PAV	SY	63		
0110-7001	EXCAV (ROADWAY)	CY	155.0		
0132-7004	EMBANK (FNL)(DC)(TY B)	CY	54.0		
0160-7002	FURN & PLACE TOPSOIL (4")	SY	222		
0164-7002	BROADCAST SEED (PERM RURAL CLAY)	SY	222		
0168-7001	VEGETATIVE WATERING	TGL	10.00		
0260-7005	LIME (COM OR QK)(SLURRY)	TON	6.0		
0260-7006	LIME TRT (EXIST MATL)(6")	SY	469		
0310-7013	PRIME COAT(MC-30 OR AE-P)	GAL	94.00		
0341-7006	D-GR HMA TY-B PG70-22	TON	248.0		
0341-7058	D-GR HMA TY-D SAC-B PG76-22	TON	42.0		
0341-7082	TACK COAT	GAL	181.00		
0502-7001	BARRICADES, SIGNS AND TRAFFIC HANDLING	MO	2		
0505-7001	TMA (STATIONARY)	DAY	30		
0505-7003	TMA (MOBILE OPERATION)	DAY	12		
0506-7002	ROCK FILTER DAMS (INSTALL) (TY 2)	LF	35		
0506-7011	ROCK FILTER DAMS (REMOVE)	LF	35		
0506-7020	CONSTRUCTION EXITS (INSTALL) (TY 1)	SY	112		
0506-7024	CONSTRUCTION EXITS (REMOVE)	SY	112		
0506-7039	TEMP SEDMT CONT FENCE (INSTALL)	LF	322		
0506-7041	TEMP SEDMT CONT FENCE (REMOVE)	LF	322		
0644-7001	IN SM RD SN SUP&AM TY10BWG(1)SA(P)	EA	2		
0662-7065	WK ZN PAV MRK REMOV (W)6"(BRK)	LF	0		
0662-7068	WK ZN PAV MRK REMOV (W)6"(SLD)	LF	0		
0662-7100	WK ZN PAV MRK REMOV (Y)6"(SLD)	LF	0		
0666-7024	REFL PAV MRK TY I (W)8"(SLD)(100MIL)	LF	87		
0666-7042	REFL PAV MRK TY I (W)(ARROW)(100MIL)	EA	1		
0666-7066	REFL PAV MRK TY I (W)(WORD)(100MIL)	EA	1		
0666-7175	RE PM TY II (W) 6" (SLD)	LF	243		
0666-7179	RE PM TY II (W) 8" (SLD)	LF	87		
0666-7186	RE PM TY II (W) (ARROW)	EA	1		
0666-7194	RE PM TY II (W) (WORD)	EA	1		
0666-7411	REFL PAV MRK TY I (W)6"(SLD)(100MIL)	LF	243		
0672-7006	REFL PAV MRKR TY II-C-R	EA	5		
0677-7001	ELIM EXT PM & MRKS (4")	LF	200		
	SUB-TOTAL				
	BID ALTERNATE #2 -Excess Material				
	Excess Material (stock pile on-site)	CY	10,661		
	SUB-TOTAL				
	GRAND TOTAL				