

BID QUANTITIES
STEUBING UNIT 14
1/2/2024

DESCRIPTION	UNIT	QTY
STREET IMPROVEMENTS		
Mobilization	LS	1
Clearing	AC	21.0
Tree Protection	LS	1
Street Excavation	CY	11,403
Street Embankment	CY	510
2" Type D HMAc	SY	11,538
10" Crushed Limestone Base (Type A, Grade 2)	SY	11,538
6" Lime Treated Subgrade	SY	2,885
6" Concrete Curb	LF	4,117
4" Mountable Curb	LF	3,905
Wheelchair Ramps	EA	2
Huebner Road Left Turn Lane	LS	1
Signage and Striping	LS	1
TPDES Storm Water Pollution Prevention Plan	LS	1
DRAINAGE IMPROVEMENTS		
Drainage Excavation	CY	3,583
Drainage Embankment	CY	1,543
12" HDPE	LF	5
24" HDPE	LF	27
30" HDPE	LF	336
Trench Excavation Protection	LF	363
4' x 4' Junction Box	EA	3
20' Curb Inlet	EA	3
Water Quality Basin	LS	1
Concrete Channel	SY	2,888
Baffle Blocks	LS	1
Rock Rubble	SY	73
3' x 3' ~ 4-way Inlet	EA	1
Revegetation/Vegetative Filter Strips	LS	1
WATER		
8" x 8" Cut In Tee	EA	1
8" DI Pipe	LF	21
8" C-900 PVC (DR18) Class 235	LF	3,922
Standard Fire Hydrant Assembly	EA	7
8" Gate valve (MJ) with 6" Valve Box, Complete	EA	10
Fittings	TON	1.87
3/4" Single Service, Long w/ 5/8" Meter & Box	EA	37
3/4" Single Service, Short w/ 5/8" Meter & Box	EA	83
2" Blow Off Assembly	EA	1
3/4" Irrigation Meter	EA	1
8" X 2" Combo Meter & Vault	EA	1
3/4" Double Check Valve Assembly	EA	1
8" Reduce Pressure Backflow Prevention	EA	1
Hydrostatic Testing	LS	1
Trench Excavation Safety Protection	LF	3,943
Chlorination	LF	3,943

SEWER		
Tie Into Existing Sewer Manhole	EA	1
8" Sanitary Sewer Pipe (SDR 26 160 PSI)		
a. (6' - 10')	LF	2,785
b. (10' - 14')	LF	486
6" Sanitary Sewer Lateral (SDR 26 160 PSI)	LF	2,846
8" x 6" Wye	EA	117
Standard Manhole w/ Ring Encasement	EA	20
Manhole Extra Depth	VF	79
Trench Excavation Protection	LF	3,271
TV Video Sewer Line	LF	3,271

GRADING		
Lot Excavation	CY	17,182
Lot Embankment	CY	22,085
Import	CY	4,903
Retaining Wall	SF	15,698

MISC		
Construction Staking	LS	1
Testing	LS	1
CPS Conduits (2 ~ 6" SCH 80 PVC, 2 ~ 4" SCH 40 PVC)	LF	1,082
CPS Conduits (3 ~ 6" SCH 80 PVC, 2~4" SCH 40 PVC)	LF	108
CPS Conduits (4 ~ 6" SCH 80 PVC, 2~4" SCH 40 PVC)	LF	35