

**BID QUANTITIES
TALLYHO UNIT 1
2/23/2024**

DESCRIPTION	UNIT	QTY
STREET IMPROVEMENTS		
Mobilization	LS	1
Clearing (ROW, Lots, and Easements)	AC	21
Street Excavation (Up to ROW)	CY	5,115
Street Embankment (Up to ROW)	CY	3,295
6" Lime Stabilized Subgrade (Local A)	SY	13,856
8" Lime Stabilized Subgrade (Local B)	SY	8,847
Lime	TON	412
11" Flexible Base (Local A)	SY	13,856
18.5" Flexible Base (Local B)	SY	8,847
2" Type D Asphalt (Local A)	SY	7,352
1.5" Type D Asphalt (Local B)	SY	8,147
2.5" Type C Asphalt (Local B)	SY	8,147
Header Curb	LF	80
7" Standard Curb	LF	7,574
Barricade Posts	EA	14
Concrete Sidewalk (Developer Responsibility)	SY	677
ADA Wheelchair Ramps	EA	9
Signage and Striping	LS	1
TPDES Storm Water Pollution Prevention Plan	LS	1
DRAINAGE IMPROVEMENTS		
Drain Excavation	CY	1,630
Concrete Baffle Blocks	CY	0.3
(2) 6'X2' Precast Multiple Box Culvert	LF	86
5' Curb Inlet	EA	2
5' Sidewalk Box	EA	7
6" Concrete Rip-Rap	SY	137
Concrete Headwalls	CY	22
Hydromulch	SY	1,023
Sidewalk Pipe Railing	LF	148
9" Rock Rubble	SY	29
18" Rock Rubble	SY	31
Trench Excavation Protection	LF	172
WATER		
8" C-900 PVC (DR 18) Pipe CL 235	LF	2,436
8" DI Pipe	LF	49
3/4" Single Service, Short w/ 5/8" Meter	EA	78
3/4" Single Service, Long w/ 5/8" Meter	EA	37
8" Gate Valve, MJ w/ Valve Box	EA	4

2" Blowoff (Temporary)	EA	5
2" Blowoff (Permanent)	EA	1
3/4" Irrigation Service w/ 5/8" Meter	EA	6
Standard Fire Hydrant Assembly	EA	4
Fittings	TON	1
24" Steel Casing (For Main)	LF	49
Tie Into Existing Water Main	EA	3
Hydrostatic Testing	LS	1
Trench Excavation Protection	LF	2,485
Joint Restraint	LS	1
Chlorination	LF	2,485
Meter Box	EA	100
SEWER		
8" Sanitary Sewer Pipe (SDR 26)		
a. 6' - 10'	LF	997
b. 10'-14'	LF	665
c. 14'-18'	LF	153
12" Sanitary Sewer Pipe (SDR 26 160 PSI)		
a. 10' - 14'	LF	40
12" Sanitary Sewer Pipe (SDR 26)		
a. 6' - 10'	LF	307
b. 10' - 14'	LF	476
c. 14'-18'	LF	417
6" Sanitary Sewer Lateral (SDR-26)	LF	3,473
8"x6" Wyes	EA	49
12"x6" Wyes	EA	47
Standard Manhole w/ Ring Encasement	EA	9
Vertical Stack	VF	230
Manhole Extra Depth	VF	62
Tie into Existing Manhole	EA	2
Trench Excavation Protection	LF	6,528
TV Video Sewer Line	LF	3,055
PRIVATE		
Lot Excavation	CY	4,680
Lot Embankment	CY	28,170
CONDUITS - PRIVATE		
Construction Staking	LS	1
SWPPP Development & Inspections (Medina County)	LS	1
SWPPP Development & Inspections (Medina County)	LF	100
Bundle A: 2~6" PVC (SCH80) & 2~4" PVC (SCH40) (Estimate, includes trenching) ¹	LF	100
Bundle B: 3~6" PVC (SCH80) & 2~4" PVC (SCH40) (Estimate, includes trenching) ¹	LF	100

1. Estimated - Quantities will be confirmed when CPS design is complete.