

**BID QUANTITIES
TALLYHO UNIT 3
2/23/2024**

DESCRIPTION	UNIT	QTY
STREET IMPROVEMENTS		
Mobilization	LS	1
Clearing (ROW, Lots, and Easements)	AC	16
Street Excavation (Up to ROW)	CY	7,855
Street Embankment (Up to ROW)	CY	690
6" Lime Stabilized Subgrade (Local A)	SY	6,753
8" Lime Stabilized Subgrade (Local B)	SY	5,058
Lime	TON	217
11" Flexible Base (Local A)	SY	6,753
18.5" Flexible Base (Local B)	SY	5,058
2" Type D Asphalt (Local A)	SY	6,082
1.5" Type D Asphalt (Local B)	SY	4,652
2.5" Type C Asphalt (Local B)	SY	4,652
Header Curb	LF	80
7" Standard Curb	LF	7,574
Barricade Posts	EA	14
Concrete Sidewalk (Developer Responsibility)	SY	381
Signage and Striping	LS	1
TPDES Storm Water Pollution Prevention Plan	LS	1
DRAINAGE IMPROVEMENTS		
Drain Excavation	CY	1,520
Drain Embankment	CY	60
30" RCP	LF	75
5' Sidewalk Box	EA	4
5' Curb Inlet	EA	2
6" Concrete Rip-Rap	SY	73
Concrete Headwalls	CY	10
Concrete Collars	CY	3
Hydromulch	SY	1,689
Sidewalk Pipe Railing	LF	63
9" Rock Rubble	SY	30
Trench Excavation Protection	LF	75
WATER		
8" C-900 PVC (DR 18) Pipe CL 235	LF	2,786
2" HDPE Pipe	LF	357
3/4" Single Service, Short w/ 5/8" Meter	EA	45
3/4" Single Service, Long w/ 5/8" Meter	EA	21
8" Gate Valve, MJ w/ Valve Box	EA	9
2" Blowoff (Temporary)	EA	1

2" Blowoff (Permanent)	EA	2
3/4" Irrigation Service w/ 5/8" Meter	EA	4
Standard Fire Hydrant Assembly	EA	5
Fittings	TON	1.5
24" Steel Casing (For Main)	LF	22
12" Steel Casing (For Main)	LF	22
Tie Into Existing Water Main	EA	1
Hydrostatic Testing	LS	1
Trench Excavation Protection	LF	3,143
Joint Restraint	LS	1
Chlorination	LF	3,143
Meter Box	EA	70

SEWER

8" Sanitary Sewer Pipe (SDR 26)		
a. 0' - 6'	LF	10
b. 6' - 10'	LF	422
c. 10' - 14'	LF	589
d. 14'-18'	LF	591
e. 18' - 22'	LF	36
8" Sanitary Sewer Pipe (SDR 26 160 PSI)		
a. 6' - 10'	LF	20
b. 10' - 14'	LF	20
12" Sanitary Sewer Pipe (SDR 26)		
a. 0' - 6'	LF	30
b. 6' - 10'	LF	20
c. 10' - 14'	LF	20
d. 14'-18'	LF	130
e. 18' - 22'	LF	740
6" Sanitary Sewer Lateral (SDR-26)	LF	2,416
8"x6" Wyes	EA	50
12"x6" Wyes	EA	9
Standard Manhole w/ Ring Encasement	EA	9
Vertical Stack	VF	358
Manhole Extra Depth	VF	70
Tie into Existing Manhole	EA	1
Trench Excavation Protection	LF	5,044
TV Video Sewer Line	LF	2,628

PRIVATE

Lot Excavation	CY	9,575
Lot Embankment	CY	12,210

MISC

Construction Staking	LS	1
SWPPP Development & Inspections (Medina County)	LS	1

Lot Embankment (Additional) ¹	CY	50,860
Bundle A: 2~6" PVC (SCH80) & 2~4" PVC (SCH40) (Estimate, includes trenching) ²	LF	100
Bundle B: 3~6" PVC (SCH80) & 2~4" PVC (SCH40) (Estimate, includes trenching) ²	LF	100
1. Overall, this project produces an excess of earthwork material, which will be embanked onsite at a location TBD.		
2. Estimated - Quantities will be confirmed when CPS design is complete.		