

**THE SANCTUARY AT BROOKS
BID QUANTITIES**

SITE WORK

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Clearing and Grubbing	AC.	3	\$	-
2	Stabilized Construction Entrance/Exit	L.S.	1	\$	-
3	Silt Fence	L.F.	700	\$	-
4	Gravel Filter Bags	L.F.	38	\$	-
5	Rock Filter Dam - Type II	L.F.	10	\$	-
6	Construction Staging Area	L.S.	1	\$	-
7	Concrete Washout Pit	L.S.	1	\$	-
8	Lot Excavation	C.Y.	976	\$	-
9	Lot Embankment (79G requirement)	C.Y.	1,247	\$	-
10	Export Material	C.Y.	1,466	\$	-
TOTAL COST					\$ -

SANITARY SEWER IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Tie into Existing Sanitary Sewer Main	EA.	1	\$	-
2	Trench Excavation Safety Protection	L.F.	665	\$	-
2	8" Sanitary Sewer Pipe, SDR-26 (6'-10')	L.F.	536	\$	-
3	8" Sanitary Sewer Pipe, SDR-26 (10'-14')	L.F.	129	\$	-
4	Standard Sanitary Sewer Manhole	EA.	4	\$	-
5	Reconstruct/Recoat Existing Manhole	EA.	1	\$	-
6	Extra Depth Manhole	V.F.	18.8	\$	-
7	6" Sanitary Sewer Laterals, SDR-26	L.F.	780	\$	-
8	8" Sewer Main Television Inspection	L.F.	665	\$	-
TOTAL COST					\$ -

ON-SITE WATER MAIN IMPROVEMENTS

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Water Main Tie-In	EA.	2	\$	-
2	Trench Excavation Protection	L.F.	729	\$	-
3	8" Pipe, C900 DR 18 PVC Class 235 (Includes Joint Restraints)	L.F.	729	\$	-
4	8" DI Pipe	L.F.	29	\$	-
5	24" Steel Casing	L.F.	13	\$	-
6	2" Temporary Blow-Offs	EA.	2	\$	-
7	8" Gate Valve, M.J. (Complete with Restraints)	EA.	3	\$	-
8	24" Butterfly Valve, M.J. (Complete with Restraints)	EA.	1	\$	-
9	Restraints	EA.	1	\$	-
10	3/4" Single Service with 5/8" Meter : Short	EA.	11	\$	-
11	3/4" Single Service with 5/8" Meter : Long	EA.	10	\$	-
12	Irrigation Service with 3/4" Meter : Short	EA.	1	\$	-
13	D.I. Fittings (Restrained)	TON.	1.1	\$	-
14	Hydrostatic Testing	EA.	1	\$	-
15	Meter Boxes	EA.	22	\$	-
TOTAL COST					\$ -

STREET IMPROVEMENTS (ONSITE)

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Street/Excavation	C.Y.	1,998	\$	-
2	Street/Embankment	C.Y.	261	\$	-
3	Lime Stabilization (6") (includes lime)	S.Y.	2,690	\$	-
4	Lime Stabilization (8") (includes lime)	S.Y.	255	\$	-
5	Flexible Base (8" Compacted) (Local A)	S.Y.	2,690	\$	-
6	Flexible Base (16" Compacted) (Local B)	S.Y.	255	\$	-
7	Prime Coat	GAL.	529	\$	-
8	Tack Coat	GAL.	247	\$	-
9	HMAC - Type D (2" Pavement Thickness) (Local A)	S.Y.	2,425	\$	-
10	HMAC - Type D (3" Pavement Thickness) (Local B)	S.Y.	221	\$	-
11	Machine Laid Curb	L.F.	1,640	\$	-

12	Concrete Sidewalk (By Developer)	S.Y.	205		\$	-
13	ADA Ramps (By Developer)	EA.	4		\$	-
14	Stop Sign	EA.	1		\$	-
15	Street Name Signs	EA.	2		\$	-
16	End of Road Markers	EA.	3		\$	-
17	Blue Raised Pavement Marker	EA.	1		\$	-
18	Metal Beam Guard Fence	L.F.	120		\$	-
19	6" Concrete Rip-Rap (Adjacent to Retaining Wall)	S.Y.	52		\$	-
20	Remove/Replace Base+HMAC	S.Y.	31		\$	-
21	Saw/Cut Existing Pavement	S.Y.	31		\$	-
					TOTAL COST	\$ -

DRAIN A

ITEM	DESCRIPTION	UNIT	EST/QTY		\$/UNIT	AMOUNT
1	6" Concrete Rip-Rap	S.Y.	5		\$	-
2	42" Concrete Pipe, Class III	LF	373		\$	-
3	36" Concrete Pipe, Class III	LF	240		\$	-
4	Modular Block Retaining Wall	S.F.	490		\$	-
5	Concrete Structure (Baffle Blocks)	CY	0.30		\$	-
6	10' Type C Curb Inlet	EA	1		\$	-
7	Junction Box 5'X5'	EA	1		\$	-
8	Junction Box 6'X6'	EA	2		\$	-
9	8'X8' 4 Way Inlet	EA	1		\$	-
10	Concrete Collars	CY	10.50		\$	-
					TOTAL COST	\$ -

ADDITIVE ITEM

ITEM	DESCRIPTION	UNIT	EST/QTY		\$/UNIT	AMOUNT
1	Conduit Bundle (2-6" PVC & 2-4" PVC)	L.F.	102		\$	-
2	Conduit Bundle (1-6" PVC & 2-4" PVC)	L.F.	238		\$	-
					TOTAL COST	\$ -