

NOTE: QUANTITIES ARE PROVIDED FOR REFERENCE ONLY. CONTRACTOR RESPONSIBLE FOR QUANTITY CONFIRMATION.					
ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
1.	OFFSITE SANITARY SEWER IMPROVEMENTS			SUBTOTAL:	\$ -
2.	Mobilization	LS	1.00		\$ -
3.	Clearing	AC	6.18		\$ -
4.	8" Sanitary Sewer Pipe (SDR 26) (<6')	LF	2,426.00		\$ -
5.	8" Sanitary Sewer Pipe (SDR 26) (6' - 8')	LF	2,541.00		\$ -
6.	8" Sanitary Sewer Pipe (SDR 26) (8'-10')	LF	312.00		\$ -
7.	8" Sanitary Sewer Pipe (SDR 26) (10' - 12')	LF	78.00		\$ -
8.	8" Sanitary Sewer Pipe (SDR 26) (12' - 14')	LF	54.00		\$ -
9.	8" Sanitary Sewer Pipe (SDR 26) (14' - 25')	LF	195.00		\$ -
10.	Standard Manhole	EA	18.00		\$ -
11.	Manhole Extra Depth	VF	27.95		\$ -
12.	Tie Into Existing Sewer Main	EA	1.00		\$ -
13.	Manhole Ring Encasement	EA	18.00		\$ -
14.	Concrete Encasement	LF	450.00		\$ -
15.	Trench Excavation Protection	LF	5,606.00		\$ -
16.	Camera Testing	LF	5,606.00		\$ -
17.	Revegetation & Hydromulch	SY	29,921.00		\$ -
18.	Jack & Bore	LS	1.00		\$ -
19.	24" Steel Casing	LF	81.00		\$ -
20.	Rebuild Concrete Driveway	SY	35.00		\$ -
21.	Rebuild Fences(as needed)	LS	1.00		\$ -
22.	Tree Protection	LS	1.00		\$ -
23.	SWPPP	LS	1.00		\$ -
	BID ALTERNATE			SUBTOTAL:	\$ -
24.	Jack & Bore Under Concrete Driveway (Copeland Property)	LS	1.00		\$ -
25.	24" Steel Casing	LF	32.25		\$ -
	GRAND TOTAL				#REF!
Notes:					
QUANTITIES ARE PROVIDED FOR REFERENCE ONLY. CONTRACTOR RESPONSIBLE FOR QUANTITY CONFIRMATION.					