

**VERAMENDI
PRECINCT 14 UNIT 5
BID FORM**

Date _____

BIDDER'S FULL NAME _____

Address _____

City, State, Zip _____

Milestone #1-Substantial Completion (days): _____ **CONTRACT AMOUNT: \$** _____ **-**

Milestone #2-Final Completion (days): _____

1. The Undersigned proposes to furnish all labor, services, materials, tools and necessary equipment for the construction of various improvements and to perform the work required at the locations set out by the Plans and Specifications, in strict accordance with the Contract Documents.
2. In submitting this Bid, it is understood that this Bid may not be altered or withdrawn for a minimum of 90 calendar days, and that the Owner has reserved the right to reject any and all Bids.
3. The Undersigned certifies that this Bid is made in good faith, without collusion or connection with any other person, persons, partnership, company, firm, association, or corporation offering Bids on this work, for the following sum or prices to wit:

SIGNATURES _____

Authorized Signing Officer, Title

SIGNATURES _____

Authorized Signing Officer, Title

PRECINCT 14 UNIT 5

ITEM	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
STREET IMPROVEMENTS					
1.	Local A (52' ROW) Rock Subgrade				
	a. 3" Type D HMA	SY	7,716		\$ -
	b. 12" Aggregate Base	SY	8,544		\$ -
2.	7" Concrete Curb & Gutter	LF	4,941		\$ -
3.	4' Sidewalk	SY	199		\$ -
4.	6' Sidewalk	SY	180		\$ -
5.	10' Sidewalk	SY	346		\$ -
6.	Temporary Turn Around	SY	398		\$ -
7.	Boulders (Sourced from onsite stockpile)	EA	4		\$ -
8.	Hydromulch (Parkways)	SY	3,976		\$ -
9.	Signage/Striping	LS	1		\$ -
10.	Secondary Access Drive (8" Aggregate Base)	SY	2,140		\$ -
11.	Wheelchair Ramps	EA	14		\$ -
12.	Demo Curb & Gutter	LF	78		\$ -
SUBTOTAL					\$ -

DRAINAGE					
1.	36" RCP	LF	30		\$ -
2.	48" RCP	LF	254		\$ -
3.	6'x6' Junction Box	EA	1		\$ -
4.	Reinforced Concrete Class 'A'				
	a. RH-15 Headwall	CY	6		\$ -
	b. 2~30' Curb Inlet	CY	30		\$ -
	c. Concrete Collars	CY	3		\$ -
5.	Boulders (Sourced from onsite stockpile)	CY	3.0		\$ -
6.	4' Concrete V-Swale	SY	25		\$ -
7.	Channel Revegetation (Hydromulch)	SY	1,410		\$ -
8.	Trench Excavation Protection	LF	284		\$ -
9.	Rock Rubble	SY	37		\$ -
				SUBTOTAL	\$ -

SANITARY SEWER IMPROVEMENTS					
1.	8" Sanitary Sewer Pipe				
	a. 0' to 6' Deep	LF	23		\$ -
	b. 6' to 8' Deep	LF	587		\$ -
	c. 8' to 10' Deep	LF	1,008		\$ -
	d. 10' to 12' Deep	LF	246		\$ -
	e. 12'-16' Deep	LF	20		\$ -
2.	Standard Manhole	EA	10		\$ -
3.	Vented Manhole	EA	8		\$ -
4.	Vertical Stack	VF	3		\$ -
5.	Manhole Extra Depth >6'	VF	55		\$ -
6.	8" x 6" Wye	EA	35		\$ -
7.	6" Sanitary Sewer Lateral	LF	1,369		\$ -
8.	Trench Excavation Protection	LF	3,253		\$ -
9.	Camera Testing	LF	1,884		\$ -
10.	Tie To Existing Sewer Manhole	EA	1		\$ -
				SUBTOTAL	\$ -

WATER DISTRIBUTION IMPROVEMENTS					
1.	12" PVC Waterline	LF	888		\$ -
2.	8" PVC Waterline	LF	2,597		\$ -
3.	8" Gate Valve, MJ w/Valve Box	EA	8		\$ -
4.	12" Gate Valve, MJ w/Valve Box	EA	1		\$ -
5.	Standard Fire Hydrant Assembly	EA	7		\$ -
6.	1" Single Service (Short)	EA	26		\$ -
7.	1" Single Service (Long)	EA	15		\$ -
8.	Joint Restraints	LS	1		\$ -
9.	Ductile Iron Fittings	TON	4		\$ -
10.	2" Blowoff Permanent	EA	2		\$ -
11.	Tie to Existing Water Main	LS	1		\$ -
12.	Hydrostatic Testing	LS	1		\$ -

13.	Trench Excavation Protection	LF	3,485		\$	-
14.	Meter Box with Lid	EA	42		\$	-
15.	2" Irrigation Service & 1.5" Meter	EA	1		\$	-
SUBTOTAL					\$	-

CLEARING, GRADING, SIGNAGE, & TPDES

1.	Excavation (Streets)	CY	4,487		\$	-
2.	Embankment (Streets)	CY	1,645		\$	-
3.	Excavation (Lots)	CY	3,484		\$	-
4.	Embankment (Lots)	CY	57,709		\$	-
5.	Additional Fill	CY	1,372		\$	-
6.	Clearing	AC	18		\$	-
7.	TPDES	LS	1		\$	-
SUBTOTAL					\$	-

CONDUITS

1.	4~4" Primary Conduit	LF	3,205		\$	-
2.	3~3" Primary Conduit	LF	1,265		\$	-
3.	1~3" Primary Conduit	LF	2,970		\$	-
4.	2~3" Secondary Conduit	LF	300		\$	-
5.	1~3" Secondary Conduit	LF	5,317		\$	-
6.	1~1-1/4" Street Light Conduit	LF	897		\$	-
7.	4-Place Primary Pull Box Foundation	EA	1		\$	-
8.	3-Place Primary Pull Box Foundation	EA	2		\$	-
9.	Secondary Pull Box	EA	29		\$	-
10.	Street Light Foundation	EA	11		\$	-
11.	Switch Gear Foundation Pad	EA	5		\$	-
12.	Transformer Pad	EA	9		\$	-
13.	Secondary Pull Box (Fiber)	EA	5		\$	-
14.	1~2" Fiber Conduit	LF	3,485		\$	-
SUBTOTAL					\$	-

PRECINCT 14 UNIT 5 - SUBTOTAL: \$ -