

VERAMENDI PRECINCT 30
UNIT 3
BID FORM

Date _____

BIDDER'S FULL NAME _____

Address _____

City, State, Zip _____

Milestone #1-Substantial Completion (days): _____ **CONTRACT AMOUNT: \$** _____ **-**

Milestone #2-Final Completion (days): _____

1. The Undersigned proposes to furnish all labor, services, materials, tools and necessary equipment for the construction of various improvements and to perform the work required at the locations set out by the Plans and Specifications, in strict accordance with the Contract Documents.
2. In submitting this Bid, it is understood that this Bid may not be altered or withdrawn for a minimum of 90 calendar days, and that the Owner has reserved the right to reject any and all Bids.
- 3.

The Undersigned certifies that this Bid is made in good faith, without collusion or connection with any other person, persons, partnership, company, firm, association, or

SIGNATURES _____

Authorized Signing Officer, Title

SIGNATURES _____

Authorized Signing Officer, Title

ITEM	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
STREET IMPROVEMENTS					
1.	Local 50' - 60' ROW (Rock Subgrade)				
	a. 3" Type D HMAC	SY	17,298	\$ -	\$ -
	b. 12" Flexible (Granular) Base	SY	18,993	\$ -	\$ -
2.	7" Concrete Curb and Gutter	LF	10,175	\$ -	\$ -
3.	Header Curb	LF	120	\$ -	\$ -
4.	Sidewalk	SY	1,615	\$ -	\$ -
5.	Sidewalk Ramps	EA	32	\$ -	\$ -
6.	Temporary Turnaround (Per New Braunfels FMO Standard)	LS	1	\$ -	\$ -
7.	Striping and Signage	LS	1	\$ -	\$ -
8.	Revegetation (Hydromulch)	SY	11,692	\$ -	\$ -
SUBTOTAL					\$ -

DRAINAGE

1.	24" RCP	LF	418	\$	-	\$	-
2.	42" RCP	LF	199	\$	-	\$	-
3.	48" RCP	LF	711	\$	-	\$	-
4.	5'x5' Junction Box	EA	4	\$	-	\$	-
5.	Reinforced Concrete Class 'A'						
	a. RH-15 Headwall	CY	1.4	\$	-	\$	-
	b. PW Headwall	CY	17.7	\$	-	\$	-
	c. 5'x4' SBC	CY	39.8	\$	-	\$	-
	d. 2~15' Curb Inlet	CY	15.6	\$	-	\$	-
	e. 4~20' Curb Inlet	CY	40.8	\$	-	\$	-
	f. 1~25' Curb Inlet	CY	12.4	\$	-	\$	-
	g. Concrete Collars	CY	8.4	\$	-	\$	-
	h. 24" Toedown	CY	11.1	\$	-	\$	-
	i. U-Channel	CY	38.9	\$	-	\$	-
6.	Boulders (On-site sourcing permitted)	CY	2.5	\$	-	\$	-
7.	6" Concrete Rip-Rap	SY	67	\$	-	\$	-
8.	Channel Revegetation (Hydromulch)	SY	171	\$	-	\$	-
9.	Trench Excavation Protection	LF	1,328	\$	-	\$	-
10.	Rock Rubble	SY	187	\$	-	\$	-
						SUBTOTAL	\$ -

NORTH WATER QUALITY BASIN

1.	4'x4' Junction Box	EA	1	\$	-	\$	-
2.	6" SCH 40 PVC Pipe	LF	80	\$	-	\$	-
3.	Landlok 450(HP-TRM) Erosion Control Mat	SY	6,686	\$	-	\$	-
4.	6" Topsoil w/Block Sod	SY	2,919	\$	-	\$	-
5.	1' Clay Liner	SY	5,568	\$	-	\$	-
6.	6" Gate and Waterproof Valve	EA	1	\$	-	\$	-
7.	120V DDC Logic Controller	EA	1	\$	-	\$	-
8.	Riser Pipe & Trash Rack	EA	1	\$	-	\$	-
9.	Rock Rubble	SY	7	\$	-	\$	-
10.	4' Concrete V-Swale	SY	88	\$	-	\$	-
11.	Pond Revegetation (Hydromulch)	SY	6,686	\$	-	\$	-
12.	RH-15 Headwall	CY	1	\$	-	\$	-
13.	Excavation (Basin)	CY	5,345	\$	-	\$	-
14.	Embankment (Basin)	CY	397	\$	-	\$	-
						SUBTOTAL	\$ -

EAST WATER QUALITY BASIN 1

1.	4'X4' Junction Box	EA	1	\$	-	\$	-
2.	6" SCH 40 PVC Pipe	LF	91	\$	-	\$	-
3.	Landlok 450(HP-TRM) Erosion Control Mat	SY	1,682	\$	-	\$	-
4.	6" Topsoil w/Block Sod	SY	1,302	\$	-	\$	-
5.	1' Clay Liner	SY	1,404	\$	-	\$	-
6.	6" Gate and Waterproof Valve	EA	1	\$	-	\$	-
7.	120V DDC Logic Controller	EA	1	\$	-	\$	-
8.	Riser Pipe & Trash Rack	EA	1	\$	-	\$	-
9.	Rock Rubble	SY	4	\$	-	\$	-
10.	4' Concrete V-Swale	SY	57	\$	-	\$	-
11.	Pond Revegetation (Hydromulch)	SY	1,682	\$	-	\$	-
12.	RH-15 Headwall	CY	1	\$	-	\$	-
13.	Excavation (Basin)	CY	1,035	\$	-	\$	-
14.	Embankment (Basin)	CY	295	\$	-	\$	-
						SUBTOTAL	\$ -

EAST WATER QUALITY BASIN 2

1.	4'X4' Junction Box	EA	1	\$	-	\$	-
2.	6" SCH 40 PVC Pipe	LF	76	\$	-	\$	-
3.	Landlok 450(HP-TRM) Erosion Control Mat	SY	1,983	\$	-	\$	-
4.	6" Topsoil w/Block Sod	SY	1,443	\$	-	\$	-
5.	1' Clay Liner	SY	1,623	\$	-	\$	-
6.	6" Gate and Waterproof Valve	EA	1	\$	-	\$	-
7.	120V DDC Logic Controller	EA	1	\$	-	\$	-
8.	Riser Pipe & Trash Rack	EA	1	\$	-	\$	-
9.	Rock Rubble	SY	7	\$	-	\$	-
10.	4' Concrete V-Swale	SY	44	\$	-	\$	-
11.	Pond Revegetation (Hydromulch)	SY	1,983	\$	-	\$	-
12.	RH-15 Headwall	CY	1	\$	-	\$	-
13.	Excavation (Basin)	CY	1,468	\$	-	\$	-
14.	Embankment (Basin)	CY	198	\$	-	\$	-
						SUBTOTAL	\$ -

SANITARY SEWER IMPROVEMENTS

1.	8" Sanitary Sewer Pipe (SDR-26)				
	a. 6' to 8' Deep	LF	947	\$ -	\$ -
	b. 8' to 10' Deep	LF	2913	\$ -	\$ -
	c. 10' to 12' Deep	LF	469	\$ -	\$ -
	d. 12' to 14' Deep	LF	176	\$ -	\$ -
	e. 14' to 16' Deep	LF	270	\$ -	\$ -
	f. 16' to 18' Deep	LF	91	\$ -	\$ -
	g. 18' to 20' Deep	LF	72	\$ -	\$ -
	h. >20' Deep	LF	205	\$ -	\$ -
	6-Inch AWWA C900 DR 25 Polyvinyl Chloride (PVC) Force Main, With				
2.	Trace Tape, All Depths, Complete in Place	LF	2,835	\$ -	\$ -
3.	6" Concrete Cap	LF	117	\$ -	\$ -
4.	6" Sanitary Sewer Lateral	LF	4,264	\$ -	\$ -
5.	Utility Shroud	EA	122	\$ -	\$ -
6.	8"x6" Wye	EA	104	\$ -	\$ -
7.	Vertical Stack	VF	209	\$ -	\$ -
8.	Standard Manhole	EA	19	\$ -	\$ -
9.	Vented Manhole	EA	10	\$ -	\$ -
10.	Drop Manhole	EA	2	\$ -	\$ -
11.	Manhole Extra Depth >6'	VF	123	\$ -	\$ -
12.	Trench Excavation Protection	LF	7,978	\$ -	\$ -
13.	Camera Testing	LF	7,978	\$ -	\$ -
				SUBTOTAL	\$ -

WATER DISTRIBUTION IMPROVEMENTS

1.	8" PVC (C-900 DR 18)	LF	5,507	\$ -	\$ -
2.	8" Gate Valve, MJ w/ Valve Box	EA	14	\$ -	\$ -
3.	Standard Fire Hydrant Assembly	EA	11	\$ -	\$ -
4.	1" Single Service, Short	EA	84	\$ -	\$ -
5.	1" Single Service, Long w/ 2" SCH 40 Sleeve	EA	45	\$ -	\$ -
6.	1" Irrigation Service	EA	3	\$ -	\$ -
7.	Joint Restraints	LS	1	\$ -	\$ -
8.	Ductile Iron Fittings	TON	3.46	\$ -	\$ -
9.	2" Blowoff Permanent	EA	6	\$ -	\$ -
10.	Tie to Existing Water Main	LS	1	\$ -	\$ -
11.	Hydrostatic Testing	LS	1	\$ -	\$ -
12.	Trench Excavation Protection	LF	5,507	\$ -	\$ -
13.	Meter Box with Lid	EA	129	\$ -	\$ -
				SUBTOTAL	\$ -

CLEARING, GRADING, SIGNAGE, & TPDES

1.	Clearing	AC	38.77	\$	-	\$	-
2.	Clearing (Precinct 30 Unit 2)	AC	17.14	\$	-	\$	-
3.	TPDES	LS	1	\$	-	\$	-
4.	TPDES (Precinct 30 Unit 2)	LS	1	\$	-	\$	-
5.	Excavation (Local Streets)	CY	13,776	\$	-	\$	-
6.	Embankment (Local Streets)	CY	7,269	\$	-	\$	-
7.	Excavation (Lots)	CY	84,085	\$	-	\$	-
8.	Embankment (Lots)	CY	138,452	\$	-	\$	-
9.	Excavation (Drainage)	CY	217	\$	-	\$	-
10.	Embankment (Drainage)	CY	690	\$	-	\$	-
11.	Export	CY	6,795	\$	-	\$	-
12.	Gravity Wall (Permitter)	VSF	13,345	\$	-	\$	-
13.	Retaining Wall	VSF	8,006	\$	-	\$	-
14.	Side Lot Walls	VSF	975	\$	-	\$	-
15.	Park Walls	VSF	8,367	\$	-	\$	-
16.	Precinct 30 Unit 2 Excavation	CY	65,563	\$	-	\$	-
17.	Precinct 30 Unit 2 Embankment	CY	17,393	\$	-	\$	-

SUBTOTAL \$ -

CONDUITS

1.	3- 3" Primary Conduit	LF	1,320	\$	-	\$	-
2.	1- 3" Primary Conduit	LF	4,645	\$	-	\$	-
3.	1- 3" Secondary Conduit	LF	3,895	\$	-	\$	-
4.	1- 3" Primary Service Stubouts	EA	1	\$	-	\$	-
5.	2- 3" Secondary Service Stubouts	EA	48	\$	-	\$	-
6.	1- 3" Secondary Service Stubouts	EA	41	\$	-	\$	-
7.	3- 3" Primary Stubout	EA	2	\$	-	\$	-
8.	4- 4" Primary Stubout	EA	1	\$	-	\$	-
9.	Transformer Pad	EA	24	\$	-	\$	-
10.	Secondary Pull Box	EA	62	\$	-	\$	-
11.	3Ø 4-Place Primary Pull Box	EA	1	\$	-	\$	-
12.	3Ø 3-Place Primary Pull Box	EA	3	\$	-	\$	-
13.	1Ø 3-Place Primary Pull Box	EA	1	\$	-	\$	-
14.	1- 1/4" Street Light Conduit	LF	915	\$	-	\$	-
15.	Street Light Foundation	EA	17	\$	-	\$	-

SUBTOTAL \$ -

VERAMENDI PRECINCT 30 UNIT 3 - CONTRACT AMOUNT: \$ -
