

VERAMENDI

WORD PKWY PHASE 3

BID FORM

Date _____

BIDDER'S FULL NAME _____

Address _____

City, State, Zip _____

Milestone #1-Substantial Completion (days): _____ **CONTRACT AMOUNT:** \$ _____ -

Milestone #2-Final Completion (days): _____

1. The Undersigned proposes to furnish all labor, services, materials, tools and necessary equipment for the construction of various improvements and to perform the work required at the locations set out by the Plans and Specifications, in strict accordance with the Contract Documents.
2. In submitting this Bid, it is understood that this Bid may not be altered or withdrawn for a minimum of 90 calendar days, and that the Owner has reserved the right to reject any and all Bids.
3. The Undersigned certifies that this Bid is made in good faith, without collusion or connection with any other person, persons, partnership, company, firm, association, or corporation offering Bids on this work, for the following sum or prices to wit:

SIGNATURES _____

Authorized Signing Officer, Title

SIGNATURES _____

Authorized Signing Officer, Title

ITEM	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
STREET IMPROVEMENTS					
1.	Arterial (100' Min. ROW)				
	a. 1.5" Type "D" HMAC	SY	9,750	\$ -	\$ -
	b. 2" Type "C/D" HMAC	SY	9,750	\$ -	\$ -
	c. 10" Flexible (Granular) Base	SY	10,147	\$ -	\$ -
2.	7" Curb and Gutter	LF	3,673	\$ -	\$ -
3.	Header Curb	LF	2,147	\$ -	\$ -
4.	4' Sidewalk	SY	18	\$ -	\$ -
5.	6' Sidewalk	SY	72	\$ -	\$ -
6.	10' Sidewalk	SY	1,948	\$ -	\$ -
7.	Hydromulch	SY	9,617	\$ -	\$ -
8.	Signage/Striping	LS	1	\$ -	\$ -
9.	Demo Temp Turnaround	SY	385	\$ -	\$ -
10.	Concrete Median	SY	121	\$ -	\$ -
ROUNDABOUT					
1.	PREPARING ROW	STA	6	\$ -	\$ -
2.	EXCAVATION (Roadway)	CY	1,766	\$ -	\$ -
3.	EMBANKMENT (Final) (Dens Cont) (TY C2)	CY	22,805	\$ -	\$ -
4.	CELL FBR MLCH SEED (PERM)(URBAN)(CLAY)	SY	3,733	\$ -	\$ -
5.	FLEXIBLE (GRANULAR) BASE	CY	1,610	\$ -	\$ -

6.	D-GR HMA(SQ) TY-C PG70-22	TON	596	\$	-	\$	-
7.	D-GR HMA(SQ) TY-D PG70-22	TON	447	\$	-	\$	-
8.	D-GR HMA(SQ) TY-C PG70-22	SY	5,416	\$	-	\$	-
9.	D-GR HMA(SQ) TY-D PG70-22	SY	5,416	\$	-	\$	-
10.	CONC PVMT (CONT REINF)(FAST TRK)(9")	SY	531	\$	-	\$	-
11.	CONC CURB (TY I)	LF	1,113	\$	-	\$	-
12.	CONC CURB & GUTTER (TY I)	LF	1,208	\$	-	\$	-
13.	CONC CURB (MOUNTABLE)	LF	417	\$	-	\$	-
14.	CONC SIDEWALKS (4")	SY	957	\$	-	\$	-
15.	CURB RAMPS (TY 1)	EA	8	\$	-	\$	-
16.	CURB RAMPS (TY 21)	EA	4	\$	-	\$	-
17.	IN SM RD SN SUP&AM TYS80(1)SA(P)	EA	35	\$	-	\$	-
18.	REFL PAV MRK TY II (W) 4" (BRK)	LF	78	\$	-	\$	-
19.	REFL PAV MRK TY II (W) 4" (DOT)	LF	335	\$	-	\$	-
20.	REFL PAV MRK TY II (W) 4" (SLD)	LF	1,098	\$	-	\$	-
21.	REFL PAV MRK TY II (W) 24" (SLD)	LF	570	\$	-	\$	-
22.	REFL PAV MRK TY II (W) (ARROW)	EA	4	\$	-	\$	-
23.	REFL PAV MRK TY II (W) 18" (YLD TRI)	EA	91	\$	-	\$	-
24.	REFL PAV MRK TY II (Y) 4" (SLD)	LF	387	\$	-	\$	-
25.	PAVEMENT SEALER 4"	LF	1,898	\$	-	\$	-
26.	PAVEMENT SEALER 24"	LF	570	\$	-	\$	-
27.	PAVEMENT SEALER (ARROW)	EA	4	\$	-	\$	-
28.	PAVEMENT SEALER (YLD TRI)	EA	91	\$	-	\$	-
29.	TACK COAT	GAL	542	\$	-	\$	-

BRIDGE

1.	Precast Arch Span Bridge (Two Cells ~ 48' X 10')	LF	66	\$	-	\$	-
2.	Railing w/ Masonry Veneer	LF	424	\$	-	\$	-
3.	Precast Wingwall (45 LF)	EA	2	\$	-	\$	-
4.	Precast Wingwall (60 LF)	EA	2	\$	-	\$	-
5.	Precast Interior Wall (6LF)	EA	2	\$	-	\$	-
6.	Retaining Wall Masonry Veneer	VSF	5,080	\$	-	\$	-
7.	Retaining Wall Footers	CY	442	\$	-	\$	-
8.	Landscape Retaining Wall	VSF	6,160	\$	-	\$	-
SUBTOTAL						\$	-

DRAINAGE

1.	24" RCP	LF	581	\$	-	\$	-
2.	30" RCP	LF	213	\$	-	\$	-
3.	36" RCP	LF	70	\$	-	\$	-
4.	42" RCP	LF	554	\$	-	\$	-
5.	48" RCP	LF	105	\$	-	\$	-
6.	6'X6' Junction Box	EA	2	\$	-	\$	-
7.	5'X5' Junction Box	EA	3	\$	-	\$	-

8.	3'X3' Junction Box	EA	1	\$	-	\$	-
9.	3'x3' Grate Inlet	EA	2	\$	-	\$	-
10.	Reinforced Concrete Class 'C'						
	a. 2~ 20' Curb Inlet	CY	21	\$	-	\$	-
	b. 2~ 25' Curb Inlet	CY	25	\$	-	\$	-
	c. 8'X8' SBC	CY	82	\$	-	\$	-
	d. RH-15 Headwall	CY	2	\$	-	\$	-
	e. FW-0 Headwall	CY	46	\$	-	\$	-
	f. PW-0 Headwall	CY	71	\$	-	\$	-
	g. Concrete Collars	CY	10	\$	-	\$	-
14.	Boulders	CY	3	\$	-	\$	-
15.	Rock Rubble	SY	99	\$	-	\$	-
16.	Rip-Rap	SY	328	\$	-	\$	-
17.	Trench Excavation Protection	LF	1,522	\$	-	\$	-
18.	Railing w/ Masonry Veneer (Culvert)	LF	122	\$	-	\$	-
						SUBTOTAL	\$ -

WATER QUALITY BASIN

1.	4'X4' Junction Box	EA	1	\$	-	\$	-
2.	6" SCH 40 PVC Pipe	LF	50	\$	-	\$	-
3.	Landlok 450(HP-TRM) Erosion Control Mat	SY	341	\$	-	\$	-
4.	6" Topsoil w/Block Sod	SY	1355	\$	-	\$	-
5.	1' Clay Liner	SY	6359	\$	-	\$	-
6.	6" Gate and Waterproof Valve	EA	1	\$	-	\$	-
7.	120V DDC Logic Controller	EA	1	\$	-	\$	-
8.	Riser Pipe & Trash Rack	EA	1	\$	-	\$	-
9.	Rock Rubble	SY	7	\$	-	\$	-
10.	4' Concrete V-Swale	SY	138	\$	-	\$	-
10.	Pond Revegetation (Hydromulch)	SY	7930	\$	-	\$	-
11.	Excavation (Basin)	CY	2306	\$	-	\$	-
12.	Embankment (Basin)	CY	1863	\$	-	\$	-
13.	Electrical Meter Rack	EA	1	\$	-	\$	-
14.	Service Conduit	LF	521	\$	-	\$	-
						SUBTOTAL	\$ -

SANITARY SEWER IMPROVEMENTS

1.	8" Sanitary Sewer Pipe (SDR-26)						
	a. 4' to 6' Deep	LF	120	\$	-	\$	-
	b. 6' to 8' Deep	LF	170	\$	-	\$	-
	c. 8' to 10' Deep	LF	314	\$	-	\$	-
	d. 10' to 12' Deep	LF	249	\$	-	\$	-
	e. 12' to 14' Deep	LF	221	\$	-	\$	-
	f. 14' to 16' Deep	LF	270	\$	-	\$	-
	g. >16' Deep	LF	93	\$	-	\$	-

2.	12" Sanitary Sewer Pipe (SDR-26)				
	a. 6' to 8' Deep	LF	35	\$ -	\$ -
	b. 8' to 10' Deep	LF	22	\$ -	\$ -
3.	18" Sanitary Sewer Pipe (SDR-26)				
	a. 8' to 10' Deep	LF	91	\$ -	\$ -
4.	6" Concrete Cap	LF	228	\$ -	\$ -
5.	Standard Manhole	EA	6	\$ -	\$ -
6.	Vented Manhole	EA	2	\$ -	\$ -
7.	Doghouse Manhole	EA	2	\$ -	\$ -
8.	Tie To Existing Sewer Manhole	EA	1	\$ -	\$ -
9.	Remove Existing Manhole	EA	2	\$ -	\$ -
10.	Remove Existing Main	LF	122	\$ -	\$ -
11.	Manhole Extra Depth (>6')	VF	51	\$ -	\$ -
12.	Trench Excavation Protection	LF	1,581	\$ -	\$ -
13.	Camera Testing	LF	1,581	\$ -	\$ -
14.	Encasement Pipe	LF	188	\$ -	\$ -
15.	Revegetation	SY	3,465	\$ -	\$ -
				SUBTOTAL	\$ -

WATER DISTRIBUTION IMPROVEMENTS

1.	24" PVC Waterline (C900 Class 235, DR18)	LF	2,924	\$ -	\$ -
2.	24" Butterfly Valve	EA	2	\$ -	\$ -
3.	4" Air Release Valves	EA	2	\$ -	\$ -
4.	Drain Valves	EA	1	\$ -	\$ -
5.	16" PVC Waterline (C900 Class 235, DR18)	LF	650	\$ -	\$ -
6.	16" Gate Valve w/ 6" Valve Box	EA	2	\$ -	\$ -
7.	16" Butterfly Valve	EA	1	\$ -	\$ -
8.	12" PVC Waterline (C900 Class 235, DR18)	LF	156	\$ -	\$ -
9.	8" PVC Waterline (C900 Class 235, DR18)	LF	114	\$ -	\$ -
10.	8" Gate Valve w/ 6" Valve Box	EA	2	\$ -	\$ -
11.	Standard Fire Hydrant Assembly	EA	9	\$ -	\$ -
12.	Permanent Blowoff Valve	EA	1	\$ -	\$ -
13.	Temporary Blowoff Valve	EA	3	\$ -	\$ -
14.	Tie-in Existing Waterline	EA	1	\$ -	\$ -
15.	Ductile Iron Fittings	TON	18	\$ -	\$ -
16.	Hydrostatic Testing	LS	1	\$ -	\$ -
17.	Trench Excavation Protection	LF	3,845	\$ -	\$ -
18.	Joint Restraint	LS	1	\$ -	\$ -
19.	Revegetation	SY	2,848	\$ -	\$ -
20.	Concrete Encasement	LF	20	\$ -	\$ -
				SUBTOTAL	\$ -

CLEARING, GRADING, SIGNAGE, & TPDES

1.	Clearing	AC	13.10	\$ -	\$ -
----	----------	----	-------	------	------

2.	TPDES	LS	1	\$	-	\$	-
3.	Street Excavation	CY	2,066	\$	-	\$	-
4.	Street Embankment	CY	26,671	\$	-	\$	-
5.	Import	CY	24,162	\$	-	\$	-
						SUBTOTAL	\$ -

CONDUITS

1.	Secondary Pull Box	EA	15	\$	-	\$	-
2.	PSE9 Switch Gear Foundation Pad	EA	7	\$	-	\$	-
3.	1- 3" Secondary Conduit	LF	2,190	\$	-	\$	-
4.	4- 4" Primary Conduit	LF	2,859	\$	-	\$	-
5.	3- 3" Primary Conduit Stubout	LF	2,093	\$	-	\$	-
6.	4- 4" Primary Conduit Stubout	LF	97	\$	-	\$	-
7.	1- 2" Fiber Conduit	LF	3,054	\$	-	\$	-
						SUBTOTAL	\$ -

WORD PKWY PHASE 3 - BASE BID: \$ -
