

CONSTRUCTION PLANS FOR

SUBMITTED BY:
MOY TARIN RAMIREZ ENGINEERS, LLC.
12770 CIMARRON PATH, SUITE 100
SAN ANTONIO, TEXAS 78249
TEL: (210) 698-5051
FAX: (210) 698-5085

OWNER/DEVELOPER

KINGFISH DEVELOPMENT, LLC
2722 W. BITTERS RD. SUITE 106
SAN ANTONIO, TX 78248
210-882-6800

VERDIN SUBDIVISION OFFSITE SEWER
SANITARY SEWER IMPROVEMENTS

SAWS CONSTRUCTION NOTES
COUNTER PERMIT AND GENERAL CONSTRUCTION PERMIT
JANUARY 2022

General Section

- All materials and construction procedures within the scope of this contract shall be approved by the San Antonio Water System (SAWS) and comply with the Plans, Specifications, General Conditions and with the following as applicable:
 - Current Texas Commission on Environmental Quality (TCEQ) "Design Criteria for Domestic Wastewater System", Texas Administrative Code (TAC) Title 30 Part 1 Chapter 217 and "Public Drinking Water", TAC Title 30 Part 1 Chapter 290.
 - Current TxDOT "Standard Specifications for Construction of Highways, Streets and Drainage".
 - Current "San Antonio Water System Standard Specifications for Water and Sanitary Sewer Construction".
 - Current City of San Antonio "Standard Specifications for Public Works Construction".
 - Current City of San Antonio "Utility Excavation Criteria Manual" (UECM).
- The contractor shall not proceed with any pipe installation work until they obtain a copy of the approved Counter Permit or General Construction Permit (GCP) from the consultant and has been notified by SAWS Construction Inspection Division to proceed with the work and has arranged a meeting with the inspector and consultant for the work requirements. Work completed by the contractor without an approved Counter Permit and/or a GCP will be subject to removal and replacement at the expense of the contractors and/or the developer.
- The Contractor shall obtain the SAWS Standard Details from the SAWS website, http://www.saws.org/business_center/specs. Unless otherwise noted within the design plans.
- The Contractor is to make arrangements with the SAWS Construction Inspection Division at (210) 233-2973, on notification procedures that will be used to notify affected home residents and/or property owners 48 hours prior to beginning any work.
- Location and depth of existing utilities and service laterals shown on the plans are understood to be approximate. Actual locations and depths must be field verified by the Contractor at least 1 week prior to construction. It shall be the Contractor's responsibility to locate utility service lines as required for construction and to protect them during construction at no cost to SAWS.
- The Contractor shall verify the exact location of underground utilities and drainage structures at least 1-2 weeks prior to construction whether shown on plans or not. Please allow up to 7 business days for locates requesting pipe location markers on SAWS facilities. The following contact information are supplied for verification purposes:
 - SAWS Utility Locates: <http://www.saws.org/Service/Locates>
 - COSA Drainage (210) 207-0724 or (210) 207-6026
 - COSA Traffic Signal Operators (210) 306-9480
 - COSA Traffic Signal Damages (210) 207-3951
 - Texas State Wide One Call Locator 1-800-545-6005 or 811
- The Contractor shall be responsible for restoring existing fences, curbs, streets, driveways, sidewalks, landscaping and structures to its original or better condition if damages are made as a result of the project's construction.
- All work in Texas Department of Transportation (TxDOT) and/or Bexar County right-of-way shall be done in accordance with respective construction specifications and permit requirements.
- The Contractor shall comply with City of San Antonio or other governing municipality's tree ordinances when excavating near trees.
- The Contractor shall not place any waste materials in the 100-year Flood Plain without first obtaining an approved Flood Plain Permit.
- Holiday Work: Contractors will not be allowed to perform SAWS work on SAWS recognized holidays. Request should be sent to costworkreg@saws.org.
- Weekend Work: Contractors are required to notify the SAWS Inspection Construction Department 48 hours in advance to request weekend work. Request should be sent to costworkreg@saws.org.
- Any and all SAWS utility work installed without holiday/weekend approval will be subject to be uncovered for proper inspection.
- Compaction note (Item 804): The contractor shall be responsible for meeting the compaction requirements on all trench backfill and for paying for the tests performed by a third party. Compaction tests will be done at one location point randomly selected, or as indicated by the SAWS Inspector and/or the test administrator, per each 12-inch loose lift per 400 linear feet at a minimum. This project will not be accepted and finalized by SAWS without this requirement being met and verified by providing all necessary documented test results.
- A copy of all testing reports shall be forwarded to SAWS Construction Inspection Division.

Sewer Notes

- The Contractor is responsible for ensuring that no Sanitary Sewer Overflow (SSO) occurs as a result of their work. All contractor personnel responsible for SSO prevention and control shall be trained on proper response. Should an SSO occur, the contractor shall:
 - Identify the source of the SSO and notify SAWS Emergency Operations Center (EOC) immediately at (210) 233-2014. Provide the address of the spill and an estimated volume or flow.
 - Attempt to eliminate the source of the SSO.
 - Contain sewage from the SSO to the extent of preventing a possible contamination of waterways.
 - Clean up spill site (return contained sewage to the collection system if possible) and properly dispose of contaminated soil/materials.
 - Clean the affected sewer mains and remove any debris.
 - Meet all post-SSO requirements as per the EPA Consent Decree, including line cleaning and televising the affected sewer mains (at SAWS direction) within 24 hours.
- Should the Contractor fail to address an SSO immediately and to SAWS satisfaction, they will be responsible for all costs incurred by SAWS, including any fines from EPA, TCEQ and/or any other Federal, State or Local Agencies. No separate measurement or payment shall be made for this work. All work shall be done according to guidelines set by the TCEQ and SAWS.
- If bypass pumping is required, the Contractor shall perform such work in accordance with SAWS Standard Specification for Water and Sanitary Sewer Construction, Item No. 864, "Bypass Pumping".
- Prior to tie-ins, any shutdowns of existing force mains of any size must be coordinated with the SAWS Construction Inspection Division at (210) 233-2973 at least one week in advance of the shutdown. The Contractor must also provide a sequence of work as related to the tie-ins; this is at no additional cost to SAWS or the project and it is the responsibility of the Contractor to sequence the work accordingly.
- Sewer pipe where water line crosses shall be 160 psi and meet the requirements of ASTM D2241, TAC 217.53 and TCEQ 290.44(e)(4)(B). Contractor shall center a 20" joint of 160 psi pressure rated PVC at the proposed water crossing.
- ELEVATIONS POSTED FOR TOP OF MANHOLES ARE FOR REFERENCE ONLY: It shall be the responsibility of the Contractor to make allowances and adjustments for top of manholes to match the finished grade of the project's improvements. (NSPI)
- Spills, Overflows, or Discharges of Wastewater: All spills, overflows, or discharges of wastewater, recycled water, petroleum products, or chemicals must be reported immediately to the SAWS Inspector assigned to the Counter Permit or General Construction Permit (GCP). This requirement applies to every spill, overflow, or discharge regardless of size.

ADDITIONAL SEWER NOTES

- ~~98% COMPACTION NOTE:~~
THE CONTRACTOR SHALL BE RESPONSIBLE FOR MEETING 98% COMPACTION ON ALL TRENCH BACKFILL AND FOR PAYING FOR THE TESTS TO BE PERFORMED BY A THIRD PARTY. COMPACTION TESTS WILL BE DONE AT ONE LOCATION POINT RANDOMLY SELECTED, OR AS INDICATED BY THE SAWS INSPECTOR/TEST ADMINISTRATOR, PER EACH 12-INCH LOOSE LIFT PER 400 LINEAR FEET AT A MINIMUM. THIS PROJECT WILL NOT BE ACCEPTED AND FINALIZED BY SAWS WITHOUT THIS REQUIREMENT BEING MET AND VERIFIED BY PROVIDING ALL NECESSARY DOCUMENTED TEST RESULTS.

NOTES:

- SANITARY SEWER LATERALS TO BE LOCATED AS SHOWN ON THE SANITARY SEWER PLANS.
- PAY CUTS FOR SANITARY SEWERS LOCATED IN STREETS ARE ESTIMATED TO THE FINISHED SUBGRADE ELEVATION. PAY CUTS ARE TO EXISTING GROUND IN UNPAVED AREAS.
- EXTEND ALL SANITARY SEWER LATERALS TO THE PROPERTY LINE OR TO THE EASEMENT LINE AS INDICATED. ALL LATERALS ARE 35' LONG UNLESS OTHERWISE NOTED.
- SANITARY SEWER LINES AND LATERALS WILL BE PVC SDR 26 ASTM D 3034 UNLESS OTHERWISE NOTED ON PLAN AND PROFILE SHEETS.
- SDR FITTINGS WILL MATCH SDR SEWER MAIN, NO SEPARATE PAY ITEM.
- ALL EXCAVATED MATERIAL SHALL BE PLACED ON THE UPGRADIENT SIDE OF THE SEWER TRENCH THUS ALLOWING THE TRENCH TO INTERCEPT ANY SILT CONTAMINATED RUNOFF.
- QUANTITIES ARE BASED ON CURRENT SAWS SPECIFICATIONS.
- ALL MANHOLES TO HAVE WATERTIGHT RING AND COVERS.
- ALL MANHOLES TO BE CONCRETE RING ENCASED.
- MANHOLES TO BE VENTED AS SHOWN ON THE SANITARY SEWER PLANS.
- AN *** DENOTES AN EXISTING TEE.
- ALL SANITARY SEWER LATERALS SHALL HAVE A MIN. 2.0 % SLOPE TO THE PROPERTY LINE.
- MINIMUM COVER FROM TOP OF SANITARY SEWER LATERALS TO TOP OF CURB WILL BE:
 - IF LATERALS DO NOT CROSS WATER MAINS, 5' COVER
 - IF LATERALS CROSS WATER MAIN,

WATER MAIN	COVER
6"	5.5'
8"	5.7'
12"	6.0'
16"	7.4'
- ALL MANHOLE OPENINGS SHALL BE 30".

SAN ANTONIO WATER SYSTEM
CRITERIA FOR SEWER MAIN CONSTRUCTION
IN THE VICINITY OF WATER MAINS


- WHERE A SEWER MAIN CROSSES OVER A WATER MAIN AND THE SEPARATION DISTANCE IS LESS THAN NINE (9) FEET, ALL PORTIONS OF THE SEWER MAIN WITHIN NINE FEET (9) OF THE WATER LINE SHALL BE CONSTRUCTED USING 150 PSI PRESSURE RATED DUCTILE IRON, CAST IRON OR PVC PIPE AND JOINED WITH EQUALLY PRESSURE RATED PRESSURE RING GASKET CONNECTIONS OR CORROSION PROTECTED MECHANICAL COUPLING DEVICES OF A CAST IRON OR DUCTILE IRON MATERIAL. A SECTION OF 150 PSI PRESSURE RATED PIPE AT LEAST EIGHTEEN (18) FEET IN LENGTH MAY BE CENTERED ON THE WATER MAIN IN LIEU OF PIPE CONNECTION REQUIREMENTS. (NO SEPARATE PAY ITEM)
- WHERE A SEMI-RIGID OR RIGID SEWER MAIN CROSSES UNDER A WATER MAIN AND THE SEPARATION DISTANCE IS LESS THAN NINE FEET BUT GREATER THAN TWO FEET, THE INITIAL BACKFILL SHALL BE CEMENT STABILIZED SAND (TWO OR MORE BAGS OF CEMENT PER CUBIC YARD OF SAND) FOR ALL SECTIONS OF THE SEWER WITHIN NINE FEET OF THE WATER MAIN.
- WHERE A SEWER MAIN CROSSES UNDER A WATER MAIN AND THE SEPARATION DISTANCE IS LESS THAN TWO FEET, THE SEWER MAIN SHALL BE CONSTRUCTED OF CAST IRON, DUCTILE IRON, OR PVC WITH A MINIMUM PRESSURE RATING OF 150 PSI WITHIN NINE FEET OF THE WATER MAIN. SHALL HAVE A SEGMENT OF SEWER PIPE CENTERED ON THE WATER MAIN. SHALL BE PLACED NO CLOSER THAN SIX INCHES BETWEEN OUTER DIAMETERS, AND SHALL BE JOINED WITH PRESSURE RING GASKET CONNECTIONS OR CORROSION PROTECTED MECHANICAL COUPLING DEVICES OF A CAST IRON OR DUCTILE IRON MATERIAL. A SECTION OF 150 PSI PRESSURE RATED PIPE OF A LENGTH GREATER THAN EIGHTEEN (18) FEET MAY BE CENTERED ON THE WATER MAIN IN LIEU OF PIPE CONNECTION REQUIREMENTS. (NO SEPARATE PAY ITEM)
- WHERE A SEWER MAIN PARALLELS A WATER MAIN AND THE SEPARATION DISTANCE IS LESS THAN NINE FEET, THE SEWER MAIN SHALL BE BELOW THE WATER MAIN, SHALL BE CONSTRUCTED OF CAST IRON, DUCTILE IRON, OR PVC WITH A MINIMUM PRESSURE RATING OF 150 PSI FOR BOTH PIPE AND JOINTS FOR A DISTANCE OF NINE FEET BEYOND THE POINT OF CONFLICT, SHALL MAINTAIN A MINIMUM SEPARATION DISTANCE BETWEEN OUTER DIAMETERS OF TWO FEET VERTICALLY AND FOUR FEET HORIZONTALLY, AND SHALL BE JOINED WITH PRESSURE RING GASKET CONNECTIONS OR CORROSION PROTECTED MECHANICAL COUPLING DEVICES OF A CAST IRON OR DUCTILE IRON MATERIAL.

SANITARY SEWER MANHOLES SHALL NOT BE INSTALLED ANY CLOSER THAN NINE FEET TO WATER MAINS.

NOTE TO CONTRACTOR:

BY THE ACT OF SUBMITTING A BID FOR THIS PROPOSED CONTRACT, THE BIDDER WARRANTS THAT THE BIDDER, AND ALL SUBCONTRACTORS AND MATERIAL SUPPLIERS HE INTENDS TO USE HAVE CAREFULLY AND THOROUGHLY REVIEWED THE DRAWINGS, SPECIFICATIONS AND ALL OTHER CONTRACT DOCUMENTS AND HAVE FOUND THEM COMPLETE AND FREE FROM ANY AMBIGUITIES AND SUFFICIENT FOR THE PURPOSE INTENDED. THE BIDDER FURTHER WARRANTS THAT TO THE BEST OF HIS OR HIS SUBCONTRACTORS' AND MATERIAL SUPPLIERS' KNOWLEDGE, ALL MATERIALS AND PRODUCTS SPECIFIED OR INDICATED HEREIN ARE ACCEPTABLE FOR ALL APPLICABLE CODES AND AUTHORITIES.

THE LOCATION OF ALL EXISTING UTILITIES SHOWN ON THESE PLANS HAS BEEN BASED UPON RECORD INFORMATION ONLY AND MAY NOT MATCH LOCATIONS AND/OR DEPTHS AS CONSTRUCTED. THE CONTRACTOR SHALL CONTACT EACH INDIVIDUAL UTILITY FOR ASSISTANCE IN DETERMINING EXISTING UTILITY LOCATIONS AND DEPTHS PRIOR TO BEGINNING ANY CONSTRUCTION. CONTRACTOR SHALL FIELD VERIFY LOCATIONS OF ALL UTILITY CROSSINGS PRIOR TO BEGINNING ANY CONSTRUCTION.



VICINITY MAP
N.T.S.

SUBMITTAL DATE:

July 27, 2023

REVISION DATE:



SHEET INDEX

SHEET NO. TITLE

- | | |
|------|--|
| C2.0 | OFF-SITE SEWER COVER |
| C2.1 | OFF-SITE SEWER OVERALL |
| C2.2 | OFF-SITE SEWER LINE "A" PLAN AND PROFILE |
| C2.4 | OFF-SITE SEWER LINE "A" PLAN AND PROFILE |
| C2.5 | SANITARY SEWER DETAILS |
| C2.6 | SIPHON PLAN & PROFILE – LINE A |

CAUTION!
THE CONTRACTOR SHALL BE REQUIRED TO LOCATE ALL PUBLIC OR PRIVATE UTILITIES INCLUDING BUT NOT LIMITED TO: WATER, SEWER, TELEPHONE AND FIBER OPTIC LINES, SITE LIGHTING ELECTRIC, SECONDARY ELECTRIC, PRIMARY ELECTRICAL DUCT BANKS, LANDSCAPE IRRIGATION FACILITIES, AND GAS LINES. ANY UTILITY CONFLICTS THAT ARISE SHOULD BE COMMUNICATED TO THE ENGINEER IMMEDIATELY AND PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL CONTACT 1-800-DIG-TESS A MINIMUM OF 48 HOURS PRIOR TO THE START OF CONSTRUCTION. ANY DAMAGE TO EXISTING UTILITIES SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND THE REPAIR SHALL BE AT CONTRACTOR'S SOLE EXPENSE WHETHER THE UTILITY IS SHOWN ON THESE PLANS OR NOT.

TRENCH EXCAVATION SAFETY PROTECTION
Contractor and/or Contractor's independently retained employee or structural design/geotechnical/safety/equipment consultant, if any, shall review these plans and available geotechnical information and the anticipated installation site(s) within the project work area in order to implement Contractor's trench excavation safety protection systems, programs and/or procedures for the project described in the contract documents. The Contractor's implementation of these systems, programs and/or procedures shall provide for adequate trench excavation safety protection that comply with as a minimum, OSHA standards for trench excavations. Specifically, Contractor and/or Contractor's independently retained employee or safety consultant shall implement a trench safety program in accordance with OSHA standards governing the presence and activities of individuals working in and around trench excavation.

Developer's Name	KINGFISH DEVELOPMENT, LLC		
Developer's Address	2722 W. BITTERS RD. SUITE 106		
City	SAN ANTONIO	State	TX
Phone #	210-882-6800	Fax #	
SAWS Block Map #	132-514	Total EDU's	N/A
Total Linear Footage of Pipe	12" ~ 1,938 L.F.	Plat No.	N/A
Number of Lots	N/A	SAWS Job No.	23-1534

SUBMITTAL SET

TEXAS C2.0

BEXAR COUNTY






Moy Tarin Ramirez Engineers, LLC

FIRM TBPELS ENG F-5297 SVY F-10131500

12770 CIMARRON PATH, SUITE 100 TEL: (210) 698-5051
SAN ANTONIO, TEXAS 78249 FAX: (210) 698-5085

- Engineers
- Surveyors
- Planners



SUBMITTAL SET


[illegible]

MTR

Moy Tarin Ramirez Engineers, LLC

• *Engineers*
• *Surveyors*
• *Planners*

TPBELS: ENGINEERING F-5297 / SURVEYING: F-10131500
12770 CIMARRON PATH, SUITE 100 TEL: (210) 698-5051
SAN ANTONIO, TEXAS 78249 FAX: (210) 698-5085




VERDIN SUBDIVISION OFFSITE SEWER
SANITARY SEWER PLAN & PROFILE
LINE "A"
STA. 1+00.00 TO STA. 13+00.00

SHEET


C2.2

Plot Date: September 11, 2024 User ID: Paul Landa
R:\McOsker Tract\Off-Site Sewer\Drawings\22094_C2.2-C2.3-Line A P&P.dwg

Plot Date: September 11, 2024, User ID: Paul_Londo
R:\McMaster_Tools\Off-Site_Sewer\Drawings\2024\C2.3-C2.3-1.dwg, 4:38P.dwg




- LEGEND**
- EXISTING WATER MAIN
 - PROPOSED WATER MAIN
 - PROPOSED FIRE HYDRANT
 - EXISTING FIRE HYDRANT
 - PROPOSED GATE VALVE
 - EXISTING GATE VALVE
 - PROPOSED SANITARY SEWER MAIN & MANHOLE
 - EXISTING SANITARY SEWER MAIN & MANHOLE
 - PROPOSED SERVICE LATERAL WITH ONE-WAY CLEAN-OUT
 - VERTICAL STACK
 - ELECTRIC, GAS, TELEPHONE & CABLE TV EASEMENT
 - TEMPORARY BENCHMARK
 - PROPOSED MINIMUM FINISH FLOOR ELEVATION
 - SANITARY SEWER/WATER CROSSING LOCATION
 - OFFICIAL PUBLIC RECORDS OF BEXAR COUNTY, TEXAS
 - OFFICIAL PUBLIC RECORDS OF MEDINA COUNTY, TEXAS
- EX 8"W
8"W
8"SS
EX 8"SS
VS
E.G.T.C.A.E.
MIN. F.F. = 795.5
O.P.R.B.C.T.
O.P.R.M.C.T.



SEWER: LIVE OAK SLOUGH-MEDINA RIVER & TOWN OF SOMERSET-ELM - DOS RIOS W.R.C.

Developer's Name	KINGFISH DEVELOPMENT, LLC
Developer's Address	2722 W. BITTERS RD. SUITE 106
City	SAN ANTONIO
State	TX
Zip	78248
Phone #	210-882-6800
Fax #	
SAWS Block Map #	132-514
Total EDU's	N/A
Total Acreage	N/A
Total Linear Footage of Pipe 12\"	1,938 L.F.
Plat No.	N/A
Number of Lots	N/A
SAWS Job No.	23-1534

LINE "A"
STA. 13+00.00 TO STA. 24+60.61




SUBMITTAL SET

REVISIONS		DESCRIPTION	BY
NO.	DATE		
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			
37			
38			
39			
40			
41			
42			
43			
44			
45			
46			
47			
48			
49			
50			
51			
52			
53			
54			
55			
56			
57			
58			
59			
60			
61			
62			
63			
64			
65			
66			
67			
68			
69			
70			
71			
72			
73			
74			
75			
76			
77			
78			
79			
80			
81			
82			
83			
84			
85			
86			
87			
88			
89			
90			
91			
92			
93			
94			
95			
96			
97			
98			
99			
100			

Engineers
Surveyors
Planners

MTR

May Tarin Ramirez Engineers, LLC
TBPELS: ENGINEERING F-5297 / SURVEYING: F-10131500
12770 CIMARRON PATH, SUITE 100 TEL: (210) 698-5051
SAN ANTONIO, TEXAS 78249 FAX: (210) 698-5055


















VERDIN SUBDIVISION OFFSITE SEWER
SANITARY SEWER PLAN & PROFILE
LINE "A"

STA. 13+00.00 TO STA. 24+60.61

SHEET

C2.3

Plot Date: September 11, 2024, User: P. Land, Location: 6. Midwater Trench (10' x 10' x 10') San Antonio, Texas



PLAT NO. N/A

TRENCH EXCAVATION SAFETY PROTECTION
Contractor and/or Contractor's independently retained employee or structural design/geotechnical/safety/equipment consultant, if any, shall review these plans and available geotechnical information and the anticipated installation site(s) within the project work area in order to implement Contractor's trench excavation safety protection systems, programs and/or procedures for the project described in the contract documents. The Contractor's implementation of these systems, programs and/or procedures shall provide for adequate trench excavation safety protection that comply with as a minimum, OSHA standards for trench excavations. Specifically, Contractor and/or Contractor's independently retained employee or safety consultant shall implement a trench safety program in accordance with OSHA standards governing the presence and activities of individuals working in and around trench excavation.

SEWER: LIVE OAK SLOUGH-MEDINA RIVER & TOWN OF SOMERSET-ELM - DOS RIOS W.R.C.

Developer's Name: KINGFISH DEVELOPMENT, LLC
Developer's Address: 2722 W. BITTERS RD, SUITE 106
City: SAN ANTONIO State: TX Zip: 78248
Phone #: 210-882-6800 Fax #:
SAWS Block Map #: 132-514 Total EDUs: N/A Total Acreage: N/A
Total Linear Footage of Pipe: 127' ~ 1,938 L.F. Plat No.: N/A
Number of Lots: N/A SAWS Job No.: 23-1534

REVISIONS

NO.	DATE	DESCRIPTION

BY:
DATE:
NO.:

PROJ. # DGN. BY: DWG. BY: CHKD. BY: DATE:
22584 ACR ACR ACR

Engineers
Surveyors
Planners


Moy Tarin Ramirez Engineers, LLC
TBPLES: ENGINEERING F-5297/SURVEYING: F-10131500
12770 CIMARRON PATH, SUITE 100 TEL: (210) 698-5051
SAN ANTONIO, TEXAS 78249 FAX: (210) 698-5051

STATE OF TEXAS
PAUL LAND, JR.
100182
LICENSED PROFESSIONAL ENGINEER

VERDIN SUBDIVISION OFFSITE SEWER
SANITARY SEWER DETAILS

SHEET

SUBMITTAL SET



VERDIN SIPHON UPSTREAM MANHOLES



1. Design Codes/Standards:

- M. Solar pump system shall have a minimum of two-year warranty on the materials, fabrication, and workmanship of any and all items furnished and installed. The Contractor and Solar Pump System manufacturer must guarantee all work and rectify any defects due to faulty materials or workmanship during the warranty period. The Contractor and Solar Pump System manufacturer must also pay for damage to other work resulting from faulty materials or workmanship which occurs within said period. Warranty periods shall commence upon written acceptance of the component or appurtenance by the San Antonio Water System (SAWS).

3. Sewage Pump:

- H. Pumps shall be capable of meeting all system hydraulic conditions without overloading the motors.
- I. Install sump pump per manufacturer's instructions.
- J. Install check valves to prevent sewer/water from reentering the sump well through the pumps.

Wet Well Requirements:

1. Pumps shall be readily removable and replaceable without dewatering the wet well or disconnecting any piping in the wet well.
2. Provide guide rail assembly with stainless steel chain for easy removal and servicing of pumps. Every integral component of the guide system shall be stainless steel 316, which includes the following but not limited to: guide rails, brackets, fittings, bolts, nuts, fasteners, adapters, attachments, etc. Flanged discharges are not allowed.
3. Install stainless steel float bracket. Level control device and float switch shall be fully accessible without the need for personnel entering the wet well.
4. Provide automatic timer for pump to empty the wet well twice a day.
5. Provide mechanical float switch for low water shut-off.
6. Wet well shall be vented.
7. Wet well shall be anchored to prevent floating.
8. All electrical equipment/panels and controls shall be above ground.
9. All cables shall be continuous (no splices allowed) and intended for wastewater service applications.
10. Provide lockable aluminum hatch covers with anti-slip top surface for access to the wet well, pumps, floats, and level control devices. Minimum hatch dimensions shall be 3 feet by 4 feet, or as required; allowing plentiful clearance for removal of submersible pumps and access to the wet well. Hatch safety grates shall be installed to provide fall protection and shall consist of aluminum material. Safety Grate shall be designed to have gaps of not more than 5 inches, and be flush with the top of the wet well concrete slab. Black and yellow stripes shall be painted around the access hatch using Epoxy Enamel (Tnemec, or equal) coating system. A "Caution! Fall Hazard" sign shall be painted/stenciled on all four sides of the hatch. Coating requirements and thickness shall be in accordance with Manufacturer's recommendations.
11. No fixed ladders are permitted in the wet well.
12. Contractor shall submit Operation and Maintenance procedures for the Siphon System before construction.
13. Provide special shoring as required (NSPI).
14. Pressure pipe and forcemains shall be HDPE pipe in accordance with Item 848 Sanitary Sewer, paragraph 848.4.3.
15. The stainless steel removable pipe plug and wet well system may be removed when sewer flow depth at daily peak flow reaching 12" deep inside the diversion manhole, or EDU of the sewer system reached 663 units.

Solar Pump Spec

Solar Panel Specifications

Maximum Power	P_m	370W
Open-Circuit Voltage	V_{oc}	41.1V
Short-Circuit Current	I_{sc}	11.26A
Maximum Power Voltage	V_{mp}	34.9V
Maximum Power Current	I_{mp}	10.6A
Power Tolerance		0~+3%


All technical data at standard test condition

($E=1000\text{W/m}^2$, $T_c=25^\circ\text{C}$, $AM=1.5$)

Maximum System Voltage	DC 1000V
Module Application	Class A
Nom Operating Cell Temp (NOCT)	47±2°C
Temperature Cycling Range	-40°C to +85°C
Weight	21kg/46.3lbs
Dimensions	1755x1038x35mm 69.1"x40.9"x1.4"
Cell Technology	Mono-Si 20.3%



TYPICAL SOLAR PANEL INSTALLATION



TYPICAL SOLAR SUMP PUMP DIAGRAM