

## **Voges Unit 3**

### **Bid Form**

### **STREET, DRAINAGE, WATER, SEWER IMPROVEMENTS**

12/20/2023

**BID DATE:** \_\_\_\_\_

**BIDDER:** \_\_\_\_\_

The undersigned bidder declares that the only person or parties interested in this proposal as principals are those names herein, that this proposal has been prepared without collusion with any other person, firm, or corporation; that he has carefully examined the specifications and the site of the proposed work and therefore agrees that he will provide all the necessary machinery, tools, apparatus and other means of construction, and will do all the work and furnish all the materials called for in the specifications in the manner prescribed therein and according to the requirements of the Engineer as herein set forth, for the following prices. Contractor is responsible for identifying and cost items on the plans not listed on this Bid Sheet.

#### **DISCLAIMER:**

HMT SHALL NOT BE HELD LIABLE FOR ACCURACY OF QUANTITIES.  
CONTRACTOR IS TO BID SIGNED, SEALED AND APPROVED PLAN SET.

**ADMINISTRATION**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Mobilization, Bonds, Prep ROW, Insurance	LS	1		\$ -
				SUBTOTAL	\$ -
				COST PER LOT	\$ -

**SW3P & SITEWORK**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Site Excavation	CY	63,145		\$ -
2	Site Embankment	CY	30,492		\$ -
3	*Retaining Wall	LS	1		\$ -
4	**Privacy Fence	LF	193		\$ -
5	Silt Fence	LF	4,200		\$ -
6	Rock Berm	LF	103		\$ -
7	Check Dam	LF	10		\$ -
8	Filter Dike	LF	90		\$ -
9	Construction Entrance	EA	1		\$ -
10	Concrete Washout Pit	EA	1		\$ -
11	Clear & Grub/Strip Top Soil	AC	25.55		\$ -
12	Hydromulch and Revegetation	AC	3.51		\$ -

\* Contractor to include cost of providing signed and sealed shop drawings of retaining wall

\*\* Privacy fence shall be owner approved

SUBTOTAL	\$ -
COST PER LOT	\$ -

**DISCLAIMER:**

HMT SHALL NOT BE HELD LIABLE FOR ACCURACY OF QUANTITIES.  
CONTRACTOR IS TO BID SIGNED, SEALED AND APPROVED PLAN SET.

**STREET IMPROVEMENTS**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Tie Into Existing Street	EA	2		\$ -
2	2" Type D HMA (Local)	SY	15,864		\$ -
3	10" Flex Base (Local)	SY	18,418		\$ -
4	Geogrid (Local)	SY	18,418		\$ -
5	Lime Stabilized Subgrade (Local)	SY	18,418		\$ -
6	Prime Coat (.2 Gal/SY)	GAL	3,684		\$ -
7	Chip Seal Surface Course Treatment (Fire Access)	SY	650		\$ -
8	13" Flex Base (Fire Access)	SY	650		\$ -
9	8" Lime Treated Subgrade (Fire Acces)	SY	650		\$ -
10	Concrete Curb and Gutter	LF	9,193		\$ -
11	4' Sidewalk	SY	433		\$ -
12	Sidewalk Ramps	EA	36		\$ -
13	Signage	LS	1		\$ -
14	End of Road (5 Bollards and Markers)	EA	2		\$ -
15	Fire Access Gate with Knox Box	EA	1		\$ -
SUBTOTAL					\$ -

**DISCLAIMER:**

HMT SHALL NOT BE HELD LIABLE FOR ACCURACY OF QUANTITIES.  
CONTRACTOR IS TO BID SIGNED, SEALED AND APPROVED PLAN SET.

**STORM DRAIN IMPROVEMENTS**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Coordination with GVEC for Relocation of Pole in Channel A	LS	1	\$ -	\$ -
2	Class I TRM	SY	1,051	\$ -	\$ -
3	36" End Treatment	EA	1	\$ -	\$ -
4	36" HP-Storm Pipe	LF	202	\$ -	\$ -
5	4'x4' Area Inlet*	EA	1	\$ -	\$ -
6	20' Sidewalk Box	EA	1	\$ -	\$ -
7	10' Sidewalk Box	EA	2	\$ -	\$ -
8	5' Sidewalk Box	EA	1	\$ -	\$ -
9	6'X4' MBC (4)	LF	50	\$ -	\$ -
10	TxDOT Parellel Headwall for Culvert A**	EA	2	\$ -	\$ -
11	3" Dia Pedestrian Pipe Railing	LF	200	\$ -	\$ -
12	5' Concrete U-Channel	LF	5	\$ -	\$ -
13	24" Dia Rock Rip-Rap	SY	234	\$ -	\$ -
14	12" Dia Rock Rip-Rap	SY	31	\$ -	\$ -
				\$ -	\$ -

\* Include pricing of concrete rip-rap and toe down around inlet

\*\*Include cost of concrete rip-rap of inlet and outfall of culvert crossing

SUBTOTAL

\$ -

COST PER LOT

\$ -

**DISCLAIMER:**

HMT SHALL NOT BE HELD LIABLE FOR ACCURACY OF QUANTITIES.  
CONTRACTOR IS TO BID SIGNED, SEALED AND APPROVED PLAN SET.

**SANITARY SEWER IMPROVEMENTS**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	Remove 12" Cap and Tie Into Existing Stub Out	EA	1		\$ -
2	12" Sanitary Sewer Pipe (0-6')	LF	81		\$ -
3	8" Sanitary Sewer Pipe (6-8')	LF	2,806		\$ -
4	8" Sanitary Sewer Pipe (8-10')	LF	1,167		\$ -
5	8" Sanitary Sewer Pipe (10-12')	LF	916		\$ -
6	8" PVC Concrete Encasement	LF	70		\$ -
7	18" Steel Encasement	LF	30		\$ -
8	Standard Sanitary Manholes	EA	16		\$ -
9	Extra Depth Manhole	VF	28		\$ -
10	Dog House Manhole	EA	1		\$ -
11	Trench Excavation Protection	LF	4,889		\$ -
12	TV Inspection of Sewer Main	LF	4,889		\$ -
13	Mandrel and Vacuum Testing	LF	4,889		\$ -
14	4" Sanitary Sewer Laterals* (Laterals to extend to UE)	EA	138		\$ -
15	Pipeline Marker	EA	1		\$ -
SUBTOTAL					\$ -
COST PER LOT					\$ -

\* Service laterals shall extend to Utility Easement

\*\* Contractor to provide vertical stacks as needed to ensure 6 feet of depth at the Utility Easement.  
(4% Max Allowable Slope per lateral detail on Sheet C8.8)

**DISCLAIMER:**

HMT SHALL NOT BE HELD LIABLE FOR ACCURACY OF QUANTITIES.  
CONTRACTOR IS TO BID SIGNED, SEALED AND APPROVED PLAN SET.

**WATER IMPROVEMENTS**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	8" C909 Water Line	LF	4,752		\$ -
2	8" Ductile Iron Pipe	LF	56		\$ -
3	Trench Excavation Safety Protection	LF	4,808		\$ -
4	Fire Hydrant Assembly (W/ Tee and Gate Valve)	EA	10		\$ -
14	8" Gate Valve MJ w/ box	EA	24		\$ -
5	1" Dual Short Water Service	EA	36		\$ -
6	1" Single Short Water Service	EA	4		\$ -
7	1" Dual Long Water Service	EA	28		\$ -
8	1" Single Long Water Service	EA	7		\$ -
10	Meter Boxes	EA	75		\$ -
11	Tie-in	EA	2		\$ -
12	2" Temporary Blow-off	EA	2		\$ -
13	Automatic Flush Valve	EA	2		\$ -
14	8" Cap	EA	2		\$ -
15	Pipe Fittings	TN	3.6		\$ -
SUBTOTAL					\$ -
COST PER LOT					\$ -

**DISCLAIMER:**

HMT SHALL NOT BE HELD LIABLE FOR ACCURACY OF QUANTITIES.  
CONTRACTOR IS TO BID SIGNED, SEALED AND APPROVED PLAN SET.

**DRY UTILITIES**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	6" PVC CPS	LF			\$ -
2	4" PVC AT&T	LF			\$ -
3	4" PVC SPECTRUM	LF			\$ -

**DISCLAIMER:**  
HMT SHALL NOT BE HELD LIABLE FOR ACCURACY OF QUANTITIES.  
CONTRACTOR IS TO BID SIGNED, SEALED AND APPROVED PLAN SET.

**ALTERNATE ITEMS**

ITEM	DESCRIPTION	UNIT	EST/QTY	\$/UNIT	AMOUNT
1	3" Ty D HMAC (Local)	SY	15,864		\$ -
2	12" Flexbase (Local)	SY	18,418		\$ -
TOTAL COST					\$ -
COST PER LOT					\$ -

City of New Braunfels has updated their street sections and this alternate is in case this project needs to meet the new standards.

**DISCLAIMER:**  
HMT SHALL NOT BE HELD LIABLE FOR ACCURACY OF QUANTITIES.  
CONTRACTOR IS TO BID SIGNED, SEALED AND APPROVED PLAN SET.