

Voges Unit 3

Job: rough mass
Units: Ft-CY
Fri Feb 16, 2024 11:41:29 Page 1

Volume Report
Design vs Existing

HMT rough

	Total	Cut	Area Fill	OnGrade	Volume Cut	Volume Fill	Comp/Ratio Cut	Comp/Ratio Fill	Compact Cut	Compact Fill	Export -Import	Change Per 0.1 ft
Job Site	1,070,069	333,818	684,979	51,272	51,383	52,770	1.00	1.00	51,383	52,770	-1,387	3,963

Job: rough mass vkk topo
Units: Ft-CY
Fri Feb 16, 2024 11:39:50 Page 1

Volume Report
Design vs Existing

VKK rough

	Total	Cut	Area Fill	OnGrade	Volume Cut	Volume Fill	Comp/Ratio Cut	Comp/Ratio Fill	Compact Cut	Compact Fill	Export -Import	Change Per 0.1 ft
Job Site	1,007,108	301,552	667,006	38,550	43,587	54,764	1.00	1.00	43,587	54,764	-11,177	3,730

Job: rough mass vkk topo
Units: Ft-CY
Fri Feb 16, 2024 11:43:14 Page 1

Volume Report
Subgrade vs Existing

VKK with streets cut - still rough

	Total	Cut	Area Fill	OnGrade	Volume Cut	Volume Fill	Comp/Ratio Cut	Comp/Ratio Fill	Compact Cut	Compact Fill	Export -Import	Change Per 0.1 ft
Job Site	1,007,108	377,333	598,582	31,193	50,809	51,608	1.00	1.00	50,809	51,608	-799	3,730

Sectional Qtys	Plane Area	Slope Area	Depth	Volume
Fire Access Aprch - 5"C 4"B	335	335	0.750	9
Fire Access Ln - 13"B	608	610	1.080	24
Fire Sub:	943	945		33
LOC - 2"Ty D 10"B	176,691	176,823	1.580	10,347
Lot Island	267,045	267,864	0.000	0
Lot Island	87,498	87,851	0.000	0
Lot Sub:	354,543	355,715	0.000	0
Sectional Total	532,177	533,483		10,380