

Opinion of Probable Quantities (Public and Private)

Project Name: Westridge Single Family

Project Number: 025-0013

Date: 2025-08-26

By: TNT

LF ROADS:

Cul-De-Sac

4,304.00

6.00

TX2 ENGINEERING

F-20787

Office:



Item No.	Item Description	Quantity	Unit	Unit Price	Tabulated Price
EROSION CONTROL					
1	Construction Entrance	1.00	EA		\$ -
2	Concrete Washout Pit	1.00	EA		\$ -
3	Silt Fence	7,154.00	LF		\$ -
4	Rock Berm	4.00	EA		\$ -
				Subtotal	\$ -

LOT GRADING (PRIVATE)					
1	Lot Clearing	32.70	AC		\$ -
2	Lot Excavation	77,239.00	CY		\$ -
3	Lot Embankment	100,078.00	CY		\$ -
4	Embankment Excess Material	7,144.00	CY		\$ -
5	Revegetation Lots	32.70	AC		\$ -
6	Demolition of Existing Structures and Fence	1.00	1		\$ -
				Subtotal	\$ -

STREET IMPROVEMENTS					
1	Mobilization	1.00	LS		\$ -
2	Street Clearing	3.48	AC		\$ -
3	Street Excavation	8,557.00	CY		\$ -
4	Street Embankment	8,005.00	CY		\$ -
5	1.5" Type D Asphalt HMA	14,706.00	SY		\$ -
6	Moisture Conditioned Subgrade	17,878.00	SY		\$ -
7	6" Flexible Base	17,878.00	SY		\$ -
8	Striping & Signage	1.00	LS		\$ -
				Subtotal	\$ -

ENTRY WAY IMPROVEMENTS					
1	Curb and Gutter	333.00	LF		\$ -
2	3" PVC Conduit	270.00	LF		\$ -
				Subtotal	\$ -

TxDOT IMPROVEMENTS					
1	Prep Row	1.00	LS		\$ -
2	Moisture Conditioned Subgrade	510.00	SY		\$ -
3	Saw Cut & Mill Existing Pavement	420.00	LF		\$ -
4	7" Type B PG 64-22 HMA	510.00	SY		\$ -
5	One Course Surf Treatment	510.00	SY		\$ -
6	2" Type D Asphalt HMA	510.00	SY		\$ -
7	1" Type Tom-C PG 76-22	510.00	SY		\$ -
8	Shoulder Up Existing Topsoil	1.00	LS		\$ -
9	Revegetate TxDOT Row	1,200.00	SY		\$ -
10	Striping & Signage	1.00	LS		\$ -
11	Traffic Control	1.00	LS		\$ -
12	Material Testing	1.00	LS		\$ -
				Subtotal	\$ -

DRAINAGE IMPROVEMENTS					
1	Pond Clearing	4.21	AC		\$ -
2	Pond Excavation	32420.00	CY		\$ -
3	Pond Embankment	2989.00	CY		\$ -
4	Excavate for 4" Topsoil	2712.00	CY		\$ -
5	4" Salvaged Topsoil	20350.00	SY		\$ -
6	30" CMP	82.00	LF		\$ -
7	54" CMP	310.00	LF		\$ -
8	30" Concrete Headwall	2.00	EACH		\$ -
9	2-54" Concrete Headwall	2.00	EACH		\$ -
10	12" Rock Bubble (18" Deep)	80.00	SY		\$ -
11	Revegetation	20350.00	SY		\$ -
12	6" Concrete Weir SE Pond	108.00	SY		\$ -
13	4" Trickle Ditch SE Pond	120.00	SY		\$ -
14	6" Concrete Weir SW Pond	81.00	SY		\$ -
15	4" Trickle Ditch SW Pond	125.00	SY		\$ -
				Subtotal	\$ -

WATER IMPROVEMENTS					
1	8" PVC	4,062.00	LF		\$ -
2	6" PVC	2,402.00	LF		\$ -
3	12"X8" Cut-In Tee	1.00	EACH		\$ -
4	Standard Fire Hydrant	9.00	EACH		\$ -
5	6" Gate Valve w/Box	19.00	EACH		\$ -
6	8" Gate Valve w/Box	26.00	EACH		\$ -
7	2" Temporary Blowoff	1.00	EACH		\$ -
8	Ductile Iron Fittings	1.00	LS		\$ -
9	3/4" Short Single Service	34.00	EACH		\$ -
10	3/4" Short Dual Service	3.00	EACH		\$ -
11	2" Long Single Service	1.00	EACH		\$ -
12	2" Long Dual Service	6.00	EACH		\$ -
13	Meter Boxes	53.00	EACH		\$ -
14	Joint Restraints	1.00	LS		\$ -
15	Trench Excavation Protection	6,464.00	LF		\$ -
16	Hydrostatic Testing	1.00	EACH		\$ -
17	Machine Chlorine	6,464.00	LF		\$ -
				Subtotal	\$ -

Grand Subtotal \$ -
11% Mobilization, Insurance, and Bonding \$ -

Grand Total \$ -

Assumptions:

- 1) ALL UNIT COSTS INCLUDE MATERIAL AND LABOR AND HAVE BEEN DERIVED FROM RECENT CONSTRUCTION BIDS RECEIVED BY OUR OFFICE
- 2) NBU Electrical Distribution and Communications Utilities are excluded from Quantity List. Contractor shall refer to Plans and Specifications by Utility Agencies.