

WINDING CREEK RANCH

UNIT 8

UNIT PRICES

Date _____

BIDDER'S FULL NAME _____

Address _____

City, State, Zip _____

UNIT 8 CONTRACT DAYS: _____ **UNIT 8 BASE BID: \$** _____ **-**

UNIT 8 CONTRACT AMOUNT: \$ _____ **-**

1. The Undersigned proposes to furnish all labor, services, materials, tools and necessary equipment for the construction of various improvements and to perform the work required at the locations set out by the Plans and Specifications, in strict accordance with the Contract Documents.
2. In submitting this Bid, it is understood that this Bid may not be altered or withdrawn for a minimum of 90 calendar days, and that the Owner has reserved the right to reject any and all Bids.
3. The Undersigned certifies that this Bid is made in good faith, without collusion or connection with any other person, persons, partnership, company, firm, association, or corporation offering Bids on this work, for the following sum or prices to wit:

SIGNATURES _____

Authorized Signing Officer, Title

SIGNATURES _____

Authorized Signing Officer, Title

ITEM	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
ONSITE STREETS					
1.	Secondary Access Road				
	a. 2" Type "C/D" HMAC (20' Width)	SY	6,955	\$ -	\$ -
	b. 8" Flexible Base (20' Width)	SY	6,955	\$ -	\$ -
	c. 6" Lime Stabilized Subgrade (20' Width)	SY	6,955	\$ -	\$ -
2.	Local Street (50' ROW)				
	a. 3" Type "C/D" HMAC (Gutter to Gutter)	SY	9,675	\$ -	\$ -
	b. 12" Flexible Base (1' Behind BOC)	SY	11,600	\$ -	\$ -
	c. 6" Lime Stabilized Subgrade (1' Behind BOC)	SY	11,600	\$ -	\$ -
3.	Residential Collector (60' ROW)				
	a. 3" Type "C/D" HMAC (Gutter to Gutter)	SY	14,790	\$ -	\$ -
	b. 15" Flexible Base (1' Behind BOC)	SY	16,915	\$ -	\$ -
	c. 8" Lime Stabilized Subgrade (1' Behind BOC)	SY	16,915	\$ -	\$ -
4.	7" Curb and Gutter	LF	12,360	\$ -	\$ -
5.	Demo Temporary Turnaround	SY	1,270	\$ -	\$ -
6.	Sidewalk	SY	3,965	\$ -	\$ -
7.	Sidewalk Ramp	EA	42	\$ -	\$ -
8.	Remove Header Curb and Barricade Posts	LF	40	\$ -	\$ -
9.	Hydromulch (Parkway)	SY	6,320	\$ -	\$ -
10.	Barricade Posts	EA	30	\$ -	\$ -
11.	Header Curb	LF	200	\$ -	\$ -
12.	Metal Beam Guard Rail	LF	326	\$ -	\$ -
13.	Concrete Valley Gutter	EA	3	\$ -	\$ -

14.	Existing GBRA and Alliance Crossings (Locate the Existing GBRA Waterline, Alliance Waterline, and Alliance Fiberline. Install 90 LF of 36" Split Casing on GBRA Waterline. Reference Crossing Details for more Detail)	LS	1	\$	-	\$	-
15.	Striping and Signage	LS	1	\$	-	\$	-
16.	TPDES	LS	1	\$	-	\$	-
17.	Commercial Driveway	EA	1	\$	-	\$	-
						SUBTOTAL	\$ -

ONSITE WATER DISTRIBUTION

1.	12" PVC Waterline (C909 Class 235)	LF	3,733	\$	-	\$	-
2.	12" Ductile Iron Pipe	LF	576	\$	-	\$	-
3.	12" Gate Valve, MJ w/ Valve Box	EA	29	\$	-	\$	-
4.	8" PVC Waterline (C909 Class 235)	LF	2,025	\$	-	\$	-
5.	8" Ductile Iron Pipe	LF	436	\$	-	\$	-
6.	8" Gate Valve, MJ w/ Valve Box	EA	12	\$	-	\$	-
7.	1" Air Release Valve	EA	2	\$	-	\$	-
8.	Standard Fire Hydrant Assembly	EA	14	\$	-	\$	-
9.	1" Single Service (Long), with 5/8" Meter	EA	5	\$	-	\$	-
10.	1" Single Service (Short), with 5/8" Meter	EA	18	\$	-	\$	-
11.	1" Dual Service (Long), with 5/8" Meter	EA	22	\$	-	\$	-
12.	1" Dual Service (Short), with 5/8" Meter	EA	19	\$	-	\$	-
13.	1" Irrigation Service	EA	4	\$	-	\$	-
14.	Ductile Iron Fittings	Ton	10.4	\$	-	\$	-
15.	Trench Excavation Protection	LF	6,770	\$	-	\$	-
16.	2" Permanent Autoflush	EA	2	\$	-	\$	-
17.	2" Permanent Blowoff Assembly	EA	4	\$	-	\$	-
18.	2" Temporary Blowoff Assembly	EA	1	\$	-	\$	-
19.	24" Steel Casing	LF	298	\$	-	\$	-
20.	Concrete Saddle	LF	96	\$	-	\$	-
21.	Remove Existing 12" Waterline	LF	57	\$	-	\$	-
22.	Meter Box	EA	109	\$	-	\$	-
23.	Hydrostatic Testing	LS	1	\$	-	\$	-
24.	Joint Restraints	LS	1	\$	-	\$	-
						SUBTOTAL	\$ -

ONSITE EARTHWORK, CLEARING, AND SWPPP

1.	Clearing	AC	35.0	\$	-	\$	-
2.	Staking	LS	1	\$	-	\$	-
3.	Excavation (Streets)	CY	8,565	\$	-	\$	-
4.	Embankment (Streets)	CY	15,640	\$	-	\$	-
5.	Excavation (Lots)	CY	1,420	\$	-	\$	-
6.	Embankment (Lots)	CY	33,070	\$	-	\$	-
7.	Excavation (Drainage)	CY	6,285	\$	-	\$	-
8.	Embankment (Drainage)	CY	4,240	\$	-	\$	-
9.	Offsite Import	CY	36,680	\$	-	\$	-
						SUBTOTAL	\$ -

ONSITE SANITARY SEWER

1.	8" Sanitary Sewer Pipe (PVC), SDR-26				
a.	6' - 8' Deep	LF	301	\$ -	\$ -
b.	8' - 10' Deep	LF	1,933	\$ -	\$ -
c.	10' - 12' Deep	LF	628	\$ -	\$ -
d.	12' - 14' Deep	LF	378	\$ -	\$ -
e.	14' - 16' Deep	LF	596	\$ -	\$ -
2.	10" Sanitary Sewer Pipe (PVC), SDR-26				
a.	4' - 6' Deep	LF	192	\$ -	\$ -
b.	6' - 8' Deep	LF	337	\$ -	\$ -
c.	8' - 10' Deep	LF	225	\$ -	\$ -
d.	10' - 12' Deep	LF	92	\$ -	\$ -
e.	12' - 14' Deep	LF	76	\$ -	\$ -
f.	14' - 16' Deep	LF	29	\$ -	\$ -
3.	8" Sanitary Sewer Pipe (PVC), D2241 SDR-26	LF	100	\$ -	\$ -
4.	8" Sanitary Sewer Pipe (PVC), D3034 SDR-26	LF	210	\$ -	\$ -
5.	10" Sanitary Sewer Pipe (PVC), D3034 SDR-26	LF	14	\$ -	\$ -
6.	24" C900 DR18 PVC Casing and Spacers	LF	125	\$ -	\$ -
7.	6" Sanitary Sewer Lateral (SDR-26) (Including Cleanout)	LF	4,670	\$ -	\$ -
8.	8"x6" Wye	EA	100	\$ -	\$ -
9.	10"x6" Wye	EA	1	\$ -	\$ -
10.	Vertical Stack	VF	223.4	\$ -	\$ -
11.	Standard Manhole	EA	20	\$ -	\$ -
12.	Watertight Manhole	EA	1	\$ -	\$ -
13.	Drop Manhole	EA	1	\$ -	\$ -
14.	Manhole Extra Depth	VF	90.4	\$ -	\$ -
15.	Tie into Existing Sewer Manhole	EA	1	\$ -	\$ -
16.	Trench Excavation Protection	LF	9,781	\$ -	\$ -
17.	1' Flowable Fill	LF	825	\$ -	\$ -
18.	Camera Testing	LF	5,111	\$ -	\$ -
19.	Pipeline Marker	EA	4	\$ -	\$ -
20.	Adjust Existing Manhole	EA	3	\$ -	\$ -
				SUBTOTAL	\$ -

ONSITE DRAINAGE

1.	24" RCP	LF	360.56	\$	-	\$	-
2.	30" RCP	LF	124.18	\$	-	\$	-
3.	36" RCP	LF	139.90	\$	-	\$	-
4.	42" RCP	LF	80.31	\$	-	\$	-
5.	48" RCP	LF	849.27	\$	-	\$	-
6.	3'X2' Single Box Culvert	LF	62.00	\$	-	\$	-
7.	8'X3' Single Box Culvert	LF	90.19	\$	-	\$	-
8.	4~8'X8' Multiple Box Culvert	LF	77.00	\$	-	\$	-
9.	Reinforced Concrete Class 'A'						
	a. 5' Type CI Curb Inlet	EA	1	\$	-	\$	-
	b. 5' Type CII Curb Inlet	EA	1	\$	-	\$	-
	c. 10' Type CI Curb Inlet	EA	1	\$	-	\$	-
	d. 15' Type C Curb Inlet	EA	1	\$	-	\$	-
	e. 15' Type CI Curb Inlet	EA	2	\$	-	\$	-
	f. 15' Type CII Curb Inlet	EA	1	\$	-	\$	-
	g. 25' Type CI Curb Inlet	EA	1	\$	-	\$	-
	h. 6'x6' Junction Box	EA	2	\$	-	\$	-
	i. RH-15 Headwalls	CY	40.3	\$	-	\$	-
	j. FW-S Headwall	CY	5.7	\$	-	\$	-
	k. PW-1 Headwalls	CY	9.8	\$	-	\$	-
	l. PW-2 Headwalls	CY	79.4	\$	-	\$	-
	m. Sidewalk Box	CY	6.3	\$	-	\$	-
	n. Baffle Blocks	CY	10.5	\$	-	\$	-
10.	6" Concrete Rip Rap	SY	685	\$	-	\$	-
11.	Pipe Railing	LF	66	\$	-	\$	-
12.	Curlex Single Net Erosion Control Blankets	SY	8,605	\$	-	\$	-
13.	Landlok 450 Erosion Control Blankets	SY	1,965	\$	-	\$	-
14.	Hydromulch	SY	36,490	\$	-	\$	-
15.	12" Rock Rubble	SY	450	\$	-	\$	-
16.	Trench Excavation Protection	LF	1,783.41	\$	-	\$	-
				SUBTOTAL	\$	-	-

ONSITE CONDUITS

1.	4" PVC Conduit (GVEC)	LF	4,400	\$	-	\$	-
2.	2.5" PVC Conduit (GVEC)	LF	11,030	\$	-	\$	-
3.	2 ~ 4" PVC SCH 40 Conduit (DR Horton)	LF	755	\$	-	\$	-
				SUBTOTAL	\$	-	-

WINDING CREEK RANCH UNIT 8 - BASE BID AMOUNT:	\$	-
--	-----------	----------